


Contract ID: 25JF0029

Contract Name: Construction of Multi-Purpose Building (Admin Building) 102nd Infantry (Igsoon) Brigade, 1st Infantry (TABAK) Division, Philippine Army, Barangay Sanito, Ipil, Zamboanga Sibugay



Republic of the Philippines
Department of Public Works and Highways
ZAMBOANGA SIBUGAY 2ND DISTRICT ENGINEERING OFFICE
Lower Ipil Heights, Ipil, Zamboanga Sibugay



SUPPLEMENTAL BULLETIN NO. 2025-21
June 27, 2025

Subject: Revision of Bill of Quantities

This Supplemental Bulletin No. 2025-21 is issued to provision in the Bidding documents (BDs) for the above stated Contract, as follows:

	Current Provision of BDs (including Previous Amendments)	Amended Provision of BDs under this Supplemental Bulletin
Bill of Quantities	As Published in the Bidding Documents	See Revised Bill of Quantities

REVISED BILL OF QUANTITIES

Pay Item No.	Description	Unit	Quantity
(1)	(2)	(3)	(4)
PART A FACILITIES FOR THE ENGINEER			
A.1.4(1)	Provision of Progress Photographs	month	5.14
PART B OTHER GENERAL REQUIREMENTS			
B.3	Permits and Clearances	lump sum	1.00
B.5	Project Billboard / Signboard	each	2.00
B.7(2)	Occupational Safety and Health Program	lump sum	1.00
B.9	Mobilization / Demobilization	lump sum	1.00
PART H MISCELLANEOUS STRUCTURES			
624(6)	Main Feeder Distribution System	lump Sum	1.00
PART III CIVIL, MECHANICAL, ELECTRICAL AND SANITARY/PLUMBING WORKS			
PART III -A EARTHWORK			

Contract ID: 25JF0029

Contract Name: Construction of Multi-Purpose Building (Admin Building) 102nd Infantry (Igsoon) Brigade, 1st Infantry (TABAK) Division, Philippine Army, Barangay Sanito, Ipil, Zamboanga Sibugay

803(1)a	Structure Excavation, Common Soil	m ³	122.69
804(1)a	Embankment from Roadway/Structure Excavation, Common Soil	m ³	122.69
804(2)	Embankment from Borrow, Common Soil	m ³	24.73
804(7)	Gravel Fill	m ³	43.96
PART III -B PLAIN AND REINFORCE CONCRETE WORKS			
900(1)c	Structural Concrete, 3000 psi, Class A, 28 days	m ³	105.48
902(1)a1	Reinforcing Steel (Deformed), Grade 40	kg	14,097.99
903(2)	Formworks and Falseworks	m ²	610.18
PART III -C FINISHING AND OTHER CIVIL WORKS			
1001(1)	Soil Poisoning	L	6.48
1001(1)b1	Pipe and Fittings, 50mm dia., PVC, Series 1000	m	21.00
1001(1)b2	Pipe and Fittings, 75mm dia., PVC, Series 1000	m	115.00
1001(1)b3	Pipe and Fittings, 100mm dia., PVC, Series 1000	m	33.00
1001(1)b4	Pipe and Fittings, 150mm dia., PVC, Series 1000	m	100.00
1001(5)b	Catch Basin, CHB	each	16.00
1001(11)	Septic Vault/Tank, Concrete/CHB	lump sum	1.00
1002(2)a2	Polypropylene Random Copolymer (PPR-C) Pipes with Fittings, 20mm dia., PN16	m	63.00
1002(5)b	Water Closet, Elongated, Complete, Flush Type	set	3.00
1002(9)a	Urinal, Flush Valve, Complete, Push Button Type	set	2.00
1002(15)a	Lavatory, Counter Top/Under Counter, Complete, Manually Operated	set	2.00
1002(16)a2	Floor Drain Plates, 75mm dia., Stainless	set	3.00
1002(18)	Stainless Steel Grab Bar, 40mm dia.	m	5.90
1002(21)	Faucet	pc	3.00
1003(1)a1	Ceiling, 4.5mm, Metal Frame, Fiber Cement Board	m ²	261.06
1003(1)e	Ceiling, Metal Frame, Prepainted Metal Panel	m ²	42.00
1004(2)	Finishing Hardware	lump sum	1.00
1010(2)a	Doors, Flush	m ²	18.48
1007(1)a	Aluminum Framed Glass Door, Sliding Type	m ²	3.57
1007(1)b	Aluminum Framed Glass Door, Swing Type	m ²	18.69
1008(1)a	Aluminum Glass Window, Sliding Type	m ²	24.60
1008(1)c	Aluminum Glass Window, Awning type	m ²	6.12

Contract ID: 25JF0029

Contract Name: Construction of Multi-Purpose Building (Admin Building) 102nd Infantry (Igsoon) Brigade, 1st Infantry (TABAK) Division, Philippine Army, Barangay Sanito, Ipil, Zamboanga Sibugay

1008(1)d	Aluminum Glass Window, Fixed Type	m ²	20.90
1010(1)	Frames; Jambs, Sills, Head, Transoms and Mullions	set	14.00
1010(2)b	Doors, Wood Panel	m ²	7.56
1013(2)e	Fabricated Metal Roofing Accessory, Gauge 24 (0.701 mm), Valley Rolls/Gutter	m	152.18
1013(2)a	Fabricated Metal Roofing Accessory, Gauge 26 (0.551mm), Ridge/Hip Rolls	m	105.80
1013(2)b	Fabricated Metal Roofing Accessory, Gauge 26 (0.551mm), Flashings	m	81.92
1013(2)c	Fabricated Metal Roofing Accessory, Gauge 24 (0.701mm), Gutters	m	26.48
1014(1)a2	Prepainted Metal Sheets, above 0.427mm, Corrugated, Long Span	m ²	474.96
1016(1)a	Waterproofing, Cement-base	m ²	14.72
1018(1)	Glazed Tiles and Trims	m ²	66.34
1018(2)	Unglazed Tiles	m ²	61.28
1018(4)	Synthetic Granite Tiles	m ²	228.42
1021(1)a	Cement Floor Finish, Plain	m ²	17.07
1027(1)	Cement Plaster Finish	m ²	1,420.51
1032(1)a	Painting Works, Masonry/Concrete	m ²	1,801.89
1032(1)b	Painting Works, Wood	m ²	52.08
1032(1)c	Painting Works, Steel	m ²	523.83
1038(1)	Reflective Insulation	m ²	452.34
1039(1)	Aluminum Cladding	m ²	17.90
1043(1)	PVC Doors and Frames	m ²	1.47
1046(2)a1	CHB Non-Load Bearing (including Reinforcing Steel), 100 mm	m ²	619.72
1047(6)	Structural Steel	kg	3,972.03
1047(8)b	Structural Steel, Purlins	kg	2,525.49
1047(5)	Metal Structure Accessories, Bolts and Rods	kg	83.97
1047(5)d	Metal Structure Accessories, Steel Plates	kg	223.73
1047(5)b	Metal Structure Accessories, Sagrods	kg	81.05
1047(3)	Metal Structure Accessories	lump sum	1.00
1051(1)a	Railing	lump sum	1.00
PART III -D ELECTRICAL			
1100(1)d	Rigid Steel Conduits (RSC), 32mm dia.	m	3.00
1100(1)e	Rigid Steel Conduits (RSC), 40mm dia.	m	8.00

Contract ID: 25JF0029

Contract Name: Construction of Multi-Purpose Building (Admin Building) 102nd Infantry (Igsoon) Brigade, 1st Infantry (TABAK) Division, Philippine Army, Barangay Sanito, Ipil, Zamboanga Sibugay

1100(6)a	Polyvinyl Chloride Pipes (PVC/uPVC), 20mm dia.	m	759.60
1100(8)	Boxes/Wire Gutter	lump sum	1.00
1100(9)	Fittings and Accessories	lump sum	1.00
1101(2)b2	Electric Wire, 3.5mm ² TW/THHN/THWN, Stranded	m	1,185.67
1101(2)b3	Electric Wire, 5.5mm ² TW/THHN/THWN, Stranded	m	1,004.30
1101(2)b4	Electric Wire, 8mm ² TW/THHN/THWN, Stranded	m	5.00
1101(2)b5	Electric Wire, 14mm ² TW/THHN/THWN, Stranded	m	15.00
1101(2)b9	Electric Wire, 50mm ² TW/THHN/THWN, Stranded	m	8.00
1101(2)b10	Electric Wire, 80mm ² TW/THHN/THWN, Stranded	m	14.00
1101(3)	Single Pole Wall Switch on One Switch Plate	set	21.00
1101(4)	Duplex (2 Single Pole Wall Switches on One Switch Plate)	set	1.00
1101(5)	Triplex (3 Single Pole Wall Switches on One Switch Plate)	set	1.00
1101(16)	Duplex Convenience Outlets/ Receptacles (GT)	set	37.00
1102(1)	Panel Board with Main and Branch Breakers	lump sum	1.00
1102(11)	Pole Mounted Power Transformer (OISC) with Complete Accessories, Single Phase, Pole Type	lump sum	1.00
1102(13)	Current Transformer	lump sum	1.00
1103(1)	Lighting Fixtures	lump sum	1.00
1109(5)a	Grounding Clamps for Electric Wires, 8mm dia.	pc	2.00
1109(5)e	Grounding Clamps for Electric Wires, 22mm dia.	pc	1.00
1109(6)e	Grounding Rod Copper Clad, 20mm dia. x 3m	length	3.00
PART III -E MECHANICAL			
1200(13)a	Airconditioning, Package/Split Type	lump sum	1.00
1202(6)c	Fire Extinguisher, 22.68 kg., CO2/HCFC123 Wheeled Type	set	3.00
1208(4)	Fire Alarm Bell	set	1.00

This Supplemental Bulletin shall form an integral part of the said Bidding Documents.

For the guidance and information of all concerned.


CHRISTOPHER L. EBAL
Assistant District Engineer
BAC Chairperson