



OFFICE OF THE SECRETARY

Manila

June 14, 2023

MEMORANDUM

FOR : **MANUEL M. BONOAN**
Secretary
This Department

This refers to the memorandum dated 16 March 2023 of **DPWH Region XII Director BASIR M. IBRAHIM**, endorsing the request for the **modification** of the project under FY 2023 GAA, to wit;

As per GAA/Original		As Modified			
Project Description					
UACS No. 310101100913000 Project ID: P00706206MN		OO1: Ensure Safe and Reliable National Road System – Asset Preservation - Preventive Maintenance - Primary Roads Cotabato-Marbel Rd - K1725 + 000 - K1727 + 753			
OO1: Ensure Safe and Reliable National Road System – Asset Preservation - Preventive Maintenance - Primary Roads Cotabato-Marbel Rd - K1725 + 000 - K1727 + 753		OO1: Ensure Safe and Reliable National Road System – Asset Preservation - Preventive Maintenance - Primary Roads Cotabato-Marbel Rd - K1724 + 054 - K1725 + 452			
Type of Work/ Physical Target	Unit Cost	Allocation	Type of Work/ Physical Target	Unit Cost	Estimated Cost
CW-1- Preventive Maintenance of Road: Asphalt Overlay 16.569 Lane km EAO	₱ 6,115,335.868 / Lane Km	₱ 101,325,000.00	CW-1- Preventive Maintenance of Road: Asphalt Overlay 5.612 Lane km EAO	₱ 18,055,060.584 / Lane Km ₱ 364/k	₱ 101,325,000.00
Total:		₱ 105,000,000.00	Total:		₱ 105,000,000.00

Justification:

- Decrease in physical target/increase of unit cost based on the Approved Plan, Program of Works (POW) and Detailed Unit Price Analysis (DUPA). The estimated cost of ₱18,055,060.584/ Lane Km of asphalt overlay road is due to the design requirements of the roadway widths of 14.6 meters (4 lanes at 3.35m/lane and additional 0.6m both sides for transition of the asphalt overlay to the outer lanes). The asphalt overlay is 100mm thick (50mm Wearing Course & 50mm Binder Course).
- The project also includes white and yellow ReflectORIZED Thermoplastic Pavement Markings and reconstruction of some portions of concrete road: removal and replacement of 0.28m thick Portland Cement Concrete Pavement (PCCP) with a total area of 560 square meters.
- Change in the project limits to synchronize with the decrease in physical target and to connect with the existing asphalt road.


27/07/2024 - SR2023-01-002476 dated 1-30-2023

UACS No. 310101100913000
Project ID: P00706206MN

Page 2 of 2

- Please see attached copy of a similar project evaluated by the Bureau of Construction (BOC) dated June 7, 2023. Project number 1 (P00706202MN).

Based on our evaluation, the submitted request for modification of the said project is in order; hence, approval hereof is recommended.




ADOR G. CANLAS
Assistant Secretary for Regional Operations
in CAR, Regions I, II, IX, X, XI, XII, and XIII

RECOMMENDING APPROVAL:



MARIA CATALINA E. CABRAL, Ph.D., CESO I
Undersecretary for Planning
and Public-Private Partnership Services



EUGENIO R. PIÑO, JR.
Undersecretary for Regional Operations
in CAR, Regions I, II, IX, X, XI, XII, and XIII


APPROVED / DISAPPROVED:



MANUEL M. BONOAN
Secretary

2.3 LDAM/OAL/AVS/AGC/ERP

Department of Public Works and Highways
Office of the Secretary



WIN3E03061

277700064