

Republic of the Philippines  
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS  
**OFFICE OF THE SECRETARY**  
Manila

Reference Number: VIII-168  
Project ID: P00733203VS

**MEMORANDUM**

**FOR :** **ROBERTO R. BONOAN, CESO I**  
Undersecretary for Regional Operations  
In NCR, Regions III, IV-A, IV-B, V, VI, VII and VIII

This has reference to the herein memorandum dated 4 May 2023 of **DPWH Regional Director EDGAR B. TABACON, CESO IV, DPWH Region VIII**, endorsing the request for the approval of the **Modification of Raulito F. Yangzon, OIC-District Engineer, Samar 1<sup>st</sup> District Engineering Office, Calbayog City, Samar**, of the project under FY 2023 General Appropriation Act (GAA), to wit;

As per GAA/Original			As Modified		
Project Description					
UACS No.: 300215103416000 Project ID: P00733203VS					
Convergence and Special Support Program			Convergence and Special Support Program		
Sustainable Infrastructure Projects Alleviating Gaps (SIPAG), Access Roads and/or Bridges from the National Road/s Leading To Major/Strategic Public Building/Facilities,			Sustainable Infrastructure Projects alleviating Gaps (SIPAG), Access Roads and/or Bridges from the National Road/s Leading to Major/Strategic Public Buildings/ Facilities,		
Construction of Road Brgy. Balocawe - Nipa, Tagapul-an, Samar			Construction of Road Brgy. Balocawe – Nipa, Tagapul-an, Samar		
Physical Target	Unit Cost	Allocation	Physical Target	Unit Cost	Estimated Cost
CW1- Construction of Concrete Road : 1.400 Lane Km	P 35,000,000.00 / Lane Km	P49,000,000.00	CW1- Construction of Gravel Road : 1.440 Lane Km	P 27,429,216.50 / Lane Km	P39,498,071.76
			CW2- Construction of Road Slope Protection Structure : 2,124.72 Square meters	P 4,472.084905 / Square meter	P 9,501,928.24
EAO		P1,000,000.00	EAO		P1,000,000.00
Total:		P50,000,000.00	Total:		P50,000,000
<b>Justifications:</b>					
1.Change of type of work (from construction of concrete road to construction of gravel road) and additional project component (CW2) suitable to the actual activities necessary for the project implementation covering a total length of 0.72 Km (2 Lanes) in order to enhance accessibility and improve the safety of the travelling public.					
2. Based on the plan and the actual site condition, the scope of work involves road opening (1.440 Lane Km) with a total width of 6.1 meters, including slope protection works (stone masonry and hand laid rock embankment) and drainage structure, in which the unit cost of P 27,429,216.50 per Lane Km for CW1 and P 4,472.084905 per Square meter for CW2 were arrived with the corresponding physical target of 1.440 Lane Km and 2,124.72 Square meters, respectively, copy attached is Certificate of Reasonableness of Cost Estimate for your reference and guidance.					
3. Attached are the following supporting documents: Form for Evaluation of Modification Request (2023, V1.0); BP 202; Certificate of Availability of Funds; Approved Program of Works; Plan; Geotagged Photos; Certificate of Reasonableness of Cost Estimate; and Location Map					

Based on our evaluation, the submitted request for modification of the said project is found in order. Hence, the said request is hereby recommended for the Undersecretary's consideration and approval.

**ERIC A. AYAPANA**  
Assistant Secretary for Regional Operations  
In NCR, Region III, IV-A, IV-B, V, VI, VII and VIII

**RECOMMENDING APPROVAL:**

**MARIA CATALINA E. CABRAL, Ph.D., CESO I**  
Undersecretary for Planning and  
Public-Private Partnership Service

**APPROVED/DISAPPROVED:**

**ROBERTO R. BERNARDO, CESO I**  
Undersecretary for Regional Operations  
In NCR, Regions III, IV-A, IV-B, V, VI, VII and VIII

2.6 ACC/BCL/EAA/RRB

MANUEL M. B...  
Secretary

Cc: Regional Director Virgilio C. Eduarte, CESO III, D...  
OIC-District Engineer Ruzalva V. Verdide, Maabate

2.6 ACC/BCL/RRB