

Republic of the Philippines
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
OFFICE OF THE SECRETARY
Manila

JUN 22 2023
MEMORANDUM

FOR : MANUEL M. BONOAN
Secretary
This Department

This refers to the memorandum dated February 17, 2023, of **Regional Director VIRGILIO C. EDUARTE, DPWH Regional Office V**, endorsing the request of then **District Engineer RUBEN S. SANTOS Jr., DPWH Camarines Sur 2nd DEO**, for the approval of the **Modification** of the project under FY 2023 General Appropriation Act (GAA), to wit;

As per GAA/Original			As Modified		
Project Description					
UACS: 300215102641000 Project ID: P00736362LZ CONVERGENCE AND SPECIAL SUPPORT PROGRAM Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) - Access Roads and/or Bridges from the National Road/s leading to Major/ Strategic Public Buildings/ Facilities Rehabilitation of Road, Brgy. Sta. Rosa Del Sur, Pasacao, Camarines Sur			CONVERGENCE AND SPECIAL SUPPORT PROGRAM Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) - Access Roads and/or Bridges from the National Road/s leading to Major/ Strategic Public Buildings/ Facilities Rehabilitation of Road, Brgy. Sta. Rosa Del Sur, Pasacao, Camarines Sur		
Physical Target	Unit Cost (P'000)	Allocation (P'000)	Physical Target	Unit Cost (P'000)	Allocation (P'000)
CW1 – Rehabilitation of Paved Road 16.536 Lane Km	4,376.814 / Lane Km	72,375.00	CW1 – Reconstruction to Concrete Pavement 1.800 Lane Km	40,208.333 / Lane Km	72,375.00
EAO –		2,625.00	EAO –		2,625.00
Total:		75,000.00	Total:		75,000.00
Justification: <i>Use of Stormwater Structural Concrete</i> <ul style="list-style-type: none"> Reconstruction of existing carriageway from 0.23 m. thick to 0.28 m. and from 6.10 m. wide to 6.70 m., and provision of 1.50 m. wide and 0.28 m. thick concrete shoulder on both sides; Inclusion of drainage and slope protection structures, and miscellaneous road safety features (curb and gutter, metal guardrails, hazard markers) which comprises 25.51% and 5.45% of the total estimated cost, respectively; Replacement of unsuitable subgrade material with sound embankment material which increases the earthworks to 20.42% of the total estimated cost; Inclusion of additional hauling cost to transfer materials; and Revision of type of work to include replacement of subgrade and subbase course, and to incorporate complete roadside features. Attached are the following supporting documents: Certificate of Reasonableness of Cost Estimate, Certificate of Availability of Funds, Program of Works, Detailed Unit Price Analysis, GIS Map, Geotagged Photos and Detailed Engineering Design Plan.					

Based on our evaluation, the submitted request for modification of the said project is in order. Hence, the said request is hereby recommended for the Secretary's consideration and approval.


ERIC A. AYAPANA

Assistant Secretary for Regional Operations
in NCR, Regions III, IV-A, IV-B, V, VI, VII and VIII

Recommending Approval:

*NOTED!
3/19
subject to further cost verification.*


MARIA CATALINA E. CABRAL, Ph.D., CESO I

Undersecretary for Planning
and Public-Private Partnership Services


ROBERTO R. BERNARDO, CESO I

Undersecretary for Regional Operations
in NCR, Regions III, IV-A, IV-B, V, VI, VII, and VIII


APPROVED/~~DISAPPROVED~~:


MANUEL M. BONOAN
Secretary

2.6 BCL/RRB

Project ID: P00736362LZ

Department of Public Works and Highways
Office of the Secretary



WIN3F07538