



Republic of the Philippines
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
OFFICE OF THE SECRETARY
Bonifacio Drive, Port Area, Manila



October 19, 2023

MEMORANDUM

FOR : **MANUEL M. BONOAN**
Secretary
This Department

This refers to the memorandum dated 8 September 2023 of **DPWH CAR Regional Director KHADAFFY D. TANGGOL**, endorsing the request of District Engineer **JOSELITO T. ARAO** of **Abra District Engineering Office** for the **modification** of the project under FY 2023 GAA, to wit;

As per GAA/Original			As Modified		
Project Description					
UACS No.: 300214100334000 Project ID: P00739551LZ					
CONVERGENCE AND SPECIAL SUPPORT PROGRAM, Special Road Fund - Motor Vehicle User's Charge (MVUC) as per R.A. 11239, Installation of Road Safety Devices Along Abra-Ilocos Norte Rd - K0427 + 000 - K0431 + 100			CONVERGENCE AND SPECIAL SUPPORT PROGRAM, Special Road Fund - Motor Vehicle User's Charge (MVUC) as per R.A. 11239, Installation of Road Safety Devices Along Abra-Ilocos Norte Rd – K0427+023 - K0430+967		
Type of Work/ Physical Target	Unit Cost	Allocation	Type of Work/ Physical Target	Unit Cost	Estimated Cost
CW1- Road Safety: Pavement markings / 15.951 lane km.	₱ 6,049,777.44/ lane km.	₱ 96,500,000.00	CW1- Road Safety: Guardrails / 656 meters	₱ 94,018.60 / meter	₱ 61,676,199.70
			CW2- Road Safety: Roadway Lighting / 165 units	₱ 209,865.47 / Number of unit	₱ 34,627,802.95
EAO	—	₱ 3,500,000.00	EAO	—	₱ 3,492,891.29
				Excess	₱ 203,106.06
Total:		₱ 100,000,000.00	Total:		₱ 100,000,000.00

Justification:

- Based on the conducted site validation and inspection, it was determined that additional safety measures are required to address specific concerns identified in the concerned road section. The presence of potential hazards and visibility challenges necessitates the inclusion of roller barriers and solar lights to ensure adequate safety for road users. By including road barriers and solar lights, the project aligns with established safety standards and regulations, ensuring the highest level of road safety for motorists and riding public.
- Considering the site validation findings, it is recommended that the project's Type of Work be modified into Item 637(2) - Double Roller Safety Barrier System with a quantity of 656 meters. The roller barriers do more than absorb impact energy. They convert the impact energy into rotational energy to propel the vehicle forward rather than potentially breaking through immovable guardrails. These adjustments will significantly contribute to the overall safety and integrity of the road section, safeguarding the well-being of road users.
- CW-2 - Item 624(8) - Solar LED Street Lights with a quantity of 165 units (ea) is included in order to enhance road visibility/illuminate the road particularly at night.
- Station limits are modified to consider on specific areas or sections of the road network that require immediate attention due to safety concerns, high traffic volume, and deteriorating conditions.
- The derived unit cost is based on the approved Detailed Unit Price Analysis (DUPA) and Program of Works (POW) with reference to the evaluation made by the Bureau of Construction as per memorandum dated September 29, 2023.

Atc - 10-202310-D/803

Based on our evaluation, the submitted request for modification of the said project is in order; hence, approval hereof is recommended.




REY PETER B. GILLE, D.M.

Assistant Secretary for Regional Operations
in CAR, Regions I, II, IX, X, XI, XII, and XIII

RECOMMENDING APPROVAL:




MARIA CATALINA E. CABRAL, Ph.D., CESO I
Undersecretary for Planning
and Public-Private Partnership Services



EUGENIO R. PIPO, JR.
Undersecretary for Regional Operations
in CAR, Regions I, II, IX, X, XI, XII, and XIII

APPROVED/~~DISAPPROVED~~:



MANUEL M. BONOAN
Secretary

2.3 aap/AVS/RPBG/ERP

Department of Public Works and Highways
Office of the Secretary



WIN3E03220