

# Southern Mindoro District Engineering Office Annual Procurement Plan for FY 2025

Code (PAP)	Procurement Project	PMO/ End-User	Is this an Early Procurement Activity? (Yes/No)	Mode of Procurement	Schedule for Each Procurement Activity				Source of Funds	Estimated Budget (PhP)			Remarks (brief description of Project)
					Advertisement/P osting of IB/REI	Submission/O pening of Bids	Notice of Award	Contract Signing		Total	MOOE	CO	
310108102130000	25EI0001 - Rehabilitation/Reconstruction of Roads with Slips, Slope Collapse and Landslide - Secondary Roads - Calapan South Rd - K0121+205 - K0121+250, K0121+437, K0121+457, K0124+577 - K0124+646, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	12-Mar-25	GoP - Current Budget Year	₱21,560,000.00		₱21,560,000.00	Construction of Concrete Slope Protection on steel sheet piles with Metal flex beam guardrails on concrete post and widening. Length of Concrete Slope Protection = 134 L.M. (1,082.05 sq.m.), 200mm thickness, 113pc- 7.5m steel sheet piles and 223pc- 6m steel sheet piles. Widening Length = 65m, width = 3.35m, thickness = 0.28m Length of Metal flex beam = 140.97 m (37 spans x 3.81m)
310108102131000	25EI0002 - Rehabilitation/ Reconstruction of Roads with Slips, Slope Collapse, and Landslide - Secondary Roads-Calapan South Rd - K0168 + 345 - K0168 + 417, Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	12-Mar-25	GoP - Current Budget Year	₱23,647,400.00		₱23,647,400.00	Construction of Concrete Slope Protection on steel sheet piles with Metal flex beam guardrails on concrete post. Length of Concrete Slope Protection = 129 L.M. (1,188,735 sq.m.), 200mm thickness, 323pc- 7.5m steel sheet piles. Length of Metal flex beam = 129.54m (34 spans x 3.81m)
310111100843000	25EI0003 - Construction/Upgrading/Rehabilitation of Drainage along National Roads - Secondary Roads - Calapan South Rd - K0153+480 - K0153+861, Mansalay, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	12-Mar-25	GoP - Current Budget Year	₱13,453,440.00		₱13,453,440.00	Construction/Upgrading/Rehabilitation of Drainage along National Roads. Length 624.00 L.M. Concrete Shoulder Width Varies from 1.2m to 2.2m. Pavement Thickness = 0.15 m. Installation of Tapered Solar LED Roadway Lighting (8.0m Height) @ Bothside. See Plan and Details.
310202101800000	25EI0004 - Road Widening - Secondary Roads Bongabong-Sagana-Roxas-Sn Aquilino Road - K0116+533.00 - K0118+000.00, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱70,975,750.00		₱70,975,750.00	Road Widening - Secondary Roads Bongabong-Sagana-Roxas-Sn Aquilino Road - K0116+533.00 - K0118+000.00 Length 1,488.00 L.M. ( 2,9760 Lane KM ). Construction of Closed Lined Canal @ Both Sides, L = 2,967 L.M., Extended RCPC 1-1.20m dia x 3.00m, Extended RCPC 1-1.20m dia x 4.00m, Extended RCPC 1-1.20m dia x 5.00m, Extended RCPC 2-1.20m dia x 3.00m, Extended RCPC 1-0.90m dia x 2.00m, Extended RCPC 1-0.90m dia x 5.00m, Installation of Solar LED Roadway Lighting 23.00 Pcs. See Plan and Details
310202101801000	25EI0005 - Road Widening-Secondary Roads-Bongabong-Sagana-Roxas-Sn Aquilino Rd - K0119 + 103 - K0121 + 000, K0122 + 421- K0122 + 474, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱93,146,625.00		₱93,146,625.00	Length 1,957.00 L.M. (3,861 Lane KM), with +7.00m adjustment. Construction of Closed Lined Canal @ Both Sides, L=3,808 L.M., 5 lined extended RCPC 1-0.61m dia x 4.00m, 1 lined extended RCPC 1-0.61m dia x 5.00m, Installation of Solar LED Roadway Lighting 45.00 Pcs. See Plan and Details
310202101802000	25EI0006 - Road Widening-Secondary Roads-Calapan South Rd - K0141 + 213 - K0142 + 019, K0142 + 134 - K0142 + 371, K0144 + 387 - K0144 + 416, Mansalay, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱50,667,325.00		₱50,667,325.00	Road Widening-Secondary Roads Calapan South Rd - Length 2.14 Lane KM, Lane Width (Varies) =3.05 m-3.65 m, Pavement Lane Thickness=0.28m, Concrete Shoulder Width=1.40m - 2.30, Shoulder Thickness=0.15m, Construction of Covered Lined Canal, K0141+213- K0141+702 @ Both Sides L=978.0 L.M. K0141+702- K0141+763.18 Left Side =61.18m, K0141+763.18 - K0141+826.17 @ Both Side L=63.09 m, K0141+826.17 - K0141+871.59 @ Left Side L=45.32m, Installation in Opposite of Single Arm Solar Led Roadway Lighting (10.0m Pole)(125W-150W) See Plan and Details
310202101960000	25EI0007 - Road Widening - Secondary Roads - Calapan South Road - K0137+798.00 - K0138+131.00, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱16,660,000.00		₱16,660,000.00	Road Widening - Secondary Roads - Calapan South Road - K0137+798.00 - K0138+131.00. Length 340.00 L.M. ( 0.680 Lane KM ), Construction of Closed Lined Canal @ Both Sides, L = 340.00 L.M., Installation of Solar LED Roadway Lighting 5.00 Pcs. See Plan and Details.
310202101963000	25EI0011 - Road Widening-Secondary Roads-Calapan South Rd - K0079 + 598.00 - K0079 + 745.00, K0079 + 861.00 - K0079 + 887.00, Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	03-Oct-24	22-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱4,432,540.00		₱4,432,540.00	Road Widening-Secondary Roads-Calapan South Rd - K0079 + 598.00 - K0079 + 745.00, K0079 + 861.00 - K0079 + 887.00. Length = 346.00 Lane KM (173.00 L.M.), Construction of Retaining wall 163.00 L.M. @ right side. See Plan & Details.
310303102117000	25EI0012 - Retrofitting/ Strengthening of Permanent Bridges: Concepcion Br. (B00048MR) along Calapan South Road Bansud, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱7,840,000.00		₱7,840,000.00	Retrofitting/ Strengthening of 15.85 L.M., 1-Span, 4-lanes RCDG Br. Repair of Cracks at deck using epoxy injection prior to the strengthening of deck slab (inner slab, Girder No. 3-6 from right to left ) using arrangement of carbon fiber sheet and for concrete girder (Girder from No. 3-6 from right to left ) using fiber sheet ( 2 layers ) and plates. Asphalt Overlay (50mm thk) = 47.85 m with Pavement Markings ( white ). Repair of Expansion Joint with sealant. Painting works on Bridge railings.



310303102118000	25EI0013 - Retrofitting/ Strengthening of Permanent Bridges: Labasan Br. (B00053MR) along Calapan South Road Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱8,820,000.00	₱8,820,000.00	Retrofitting/ Strengthening of 18.86 L.M., 1-Span, 4-lanes RCDG Br. Repair of Cracks at deck using epoxy prior to the strengthening of deck slab (inner slab, Girder No. 3-6 from right to left ) using arrangement of carbon fiber sheet and for concrete girder (Girder from No. 3-6 from right to left ) using fiber sheet ( 2 layers ) and plates. Asphalt Overlay (50mm thick) = 44.88 m with Pavement Markings ( white ). Repair of Expansion Joint with sealant. Painting works on Bridge railings.
310303102114000	25EI0014 - Retrofitting/ Strengthening of Permanent Bridges-Langgang Br. (B00038MR) along Calapan South Rd, Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱4,900,000.00	₱4,900,000.00	Retrofitting/ Strengthening of 13.82 L.M., 1-Span, 4-lane Flat Slab Br. Strengthening of Deck Slab (inner slab from Slab No. 2-3 ) using Carbon Fiber Sheet / Plates. Repair of cracks by Epoxy injection method. Asphalt Overlay (50 mm thick) = 45.82 m with Reflective Pavement Markings (white). Painting works on Bridge Railings.
310303102116000	25EI0015 - Retrofitting/ Strengthening of Permanent Bridges-Pag-asa Br. (B00045MR) along Calapan South Rd, Bansud, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱8,820,000.00	₱8,820,000.00	Retrofitting/ Strengthening of 15.61 L.M., 1-Span, 4-lanes RCDG Br. Repair of Cracks at deck using epoxy injection prior to the strengthening of deck slab (inner slab, Slab No. 2-6 from right to left ) using arrangement of carbon fiber sheet and for concrete girder (Girder from No. 2-7 from right to left ) using fiber sheet ( 2 layers ) and plates. Repair of Expansion Joint with sealant. Painting works on Bridge railings.
310303102113000	25EI0016 - Retrofitting/ Strengthening of Permanent Bridges-Quinabigan Br. (B00035MR) along Calapan South Rd, Pinamlayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱14,700,000.00	₱14,700,000.00	Retrofitting/ Strengthening of 30.66 L.M., 2-Span, 4-lane RCDG Br. Strengthening of Deck Slab (inner slab from Slab No. 3-5 ) and Girder (from Girder No. 3-6) using Carbon Fiber Sheet / Plates. Replacement and installation of Expansion Joint with Premolded Expansion Joint Filler with Sealant (12 mm thick). Painting works on Bridge Railings.
310303102115000	25EI0017 - Retrofitting/ Strengthening of Permanent Bridges: Tinalunan Br. (B00040MR) along Calapan South Road Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱10,780,000.00	₱10,780,000.00	Retrofitting/ Strengthening of 15.87 L.M., 1-Span, 4-lanes RCDG Br. Repair of Cracks at deck using epoxy injection prior to the strengthening of deck (inner slab, Slab No. 3-5 from right to left ) using arrangement of carbon fiber sheet and for concrete girder (All Girder ) using fiber sheet ( 2 layers ) and plates. Removed and Replaced PCCP (0.28 m thick) inner lane 3.35m = 81 L.m. in approach A & 81 L.m. in approach B with Pavement Markings (white). Painting works on Bridge railings.
320101114026000	25EI0018 - Construction/Maintenance of Flood Mitigation Structures and Drainage Systems, Construction of Cawacat River Control Structure (Upstream), Barangay Campaasan, Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱29,400,000.00	₱29,400,000.00	Construction of Gabion Revetment w/ Steel Sheet Piles, Gabion Length = 147.00 L.M. Installation of 6-layer gabion 1.00 m x 1.00 m x 2.00 m with closure at the end of the project. Installation of Steel Sheet Piles 6.0 m Length with 147.20 m. length of pile cap. See Plan and Details.
320101114027000	25EI0019 - Construction/ Maintenance of Flood Mitigation Structures and Drainage Systems-Construction of Coringot River Control Structure (Coringot Bridge Abutment A and B Upstream), Barangay Nasucob, Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱29,400,000.00	₱29,400,000.00	Gabion Length = 148.00 L.M. with Closure at the beginning and end of the project of left side bank, and closure at the end of the project for the structure at the right side bank. Construction of Pile Cap 0.60m x 0.70 m and installation of Steel Sheet Piles, Length = 148.00 m. Installation of 1 line 1-0.90m x 8.0m RCPC. Provide S-type Headwall at both sides. See plans and details.
320101114024000	25EI0021 - Construction/ Maintenance of Flood Mitigation Structures and Drainage Systems-Construction of Protection Works and Drainage System, Bansud RIS, Bansud, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	20-Sep-24	10-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱14,700,000.00	₱14,700,000.00	Construction of Protection Works and Drainage System, Bansud RIS, Bansud, Oriental Mindoro, Drainage Length = 900.001 M Removal and replacement of existing NIA Canal. Installation of concrete wheel guard and provision of embankment. See Plan and Details.
320101114025000	25EI0022 - Construction/ Maintenance of Flood Mitigation Structures and Drainage Systems-Construction of Protection Works, Pula RIS, Pinamlayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	20-Sep-24	10-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱14,700,000.00	₱14,700,000.00	Construction of Protection Works, Pula RIS, Pinamlayan, Oriental Mindoro, Gabion Length = 70.00 L.M. with Closure at the beginning of the project. Construction of Pile Cap 0.60 m x 0.70 m. and installation of Steel Sheet Piles, Length = 70.00m. See Plan and Details.
320102107864000	25EI0023 - Construction/ Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers-Construction of Balite River Flood Control Structure, Barangay M. Adriatico, Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱49,000,000.00	₱49,000,000.00	Gabion Length = 230.00 L.M. with Closure at the beginning and end of the project. Construction of Pile Cap 0.60m x 0.70 m and installation of Steel Sheet Piles, Length = 230.00 m. See plans and details.
320102107488000	25EI0024 - Construction/ Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers-Construction of Balite River Flood Control Structure, Barangay M. Adriatico, Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱57,900,000.00	₱57,900,000.00	Gabion Length = 304.00 L.M. with Closure at the beginning of the project. Construction of Pile Cap 0.60m x 0.70 m and installation of Steel Sheet Piles, Length = 304.00 m. See plans and details.
320102107865000	25EI0025 - Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Balite River Flood Control Structure, Barangay Buong Lupa, Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱22,318,520.00	₱22,318,520.00	Construction of Concrete Revetment w/ Steel sheet Piles at Balite River, Barangay Buong lupa, Length = 120.00 L.M., Construction of 1-layer Concrete Revetment, Height = 4.00 m with closure at the beginning of the project. Installation of Steel Sheet Piles, U-type, 6.00m length with 120.00 m length of pile cap. See plans and details.



320102107861000	25EI0026 - Construction/ Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers-Construction of Pula River Control Structure, Barangay Santo Niño and Barangay Bacungan, Pinamlayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	11-Mar-25	GoP - Current Budget Year	₱29,400,000.00	₱29,400,000.00	Construction of Concrete Revetment w/ Steel sheet Piles at Pula River, Barangay Santo Niño and Barangay Bacungan, Length = 141.00 L.M., Construction of 2-layer Concrete Revetment, Bottom Layer Height = 4.00 m, Top Layer Height = 3.00 m with closure at the beginning of the project. Installation of Steel Sheet Piles, U-type, 6.00 m . length with 141.20 m length of pile cap. See plans and details.
320102107476000	25EI0027 - Construction/ Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers-Construction of Bansud River Control Structure (Downstream), Barangay Poblacion, Bansud, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱57,900,000.00	₱57,900,000.00	Construction of Gabion Revetment w/ Steel Sheet Piles of Bansud River adjacent to the abutment protection of Approach B of Bansud Bridge (Downstream), Gabion Length = 276.00 L.M., Installation of 7-Layer Gabion 1.00 m x 1.00 m x 2.00 m with closure at the end of the project. Installation of Sheet Piles 6.00 m length with 276.00 m length of pile cap. Installation of 1 line of RCPC 1-0.90m dia. x 6.0m at the abutment protection of 2nd approach of Bansud Bridge. Provide S-type Headwall at both ends of RCPC. See plans and details.
320102107862000	25EI0028 - Construction/ Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers-Construction of Bongabong River Control Structure, Barangay Anilao Section, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱29,400,000.00	₱29,400,000.00	Gabion Length = 156.00 L.M. with Closure at the beginning and end of the project. Construction of Pile Cap 0.60m x 0.70 m and installation of Steel Sheet Piles, Length = 156.00 m. See plans and details.
320102107863000	25EI0029 - Construction/ Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers-Construction of Bongabong River Control Structure, Barangay San Jose Section, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱29,400,000.00	₱29,400,000.00	Gabion Length = 127.00 L.M., Installation of 7-layer Gabion 1.00 m x 2.00 m with closure at the beginning of the project. Installation of Steel Sheet Piles 6.00 m length with 127.00 m length of pile cap. See plans and details.
300203101213000	25EI0033 - Construction/Improvement of Access Roads leading Declared Tourism Destinations (Tourism Road Infrastructure Program - TRIP) - Brgy. Malubay to Brgy. Buong Lupa leading to Walang Langit Falls, Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	03-Oct-24	22-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱9,800,000.00	₱9,800,000.00	Construction/Improvement of Access Roads leading Declared Tourism Destinations (Tourism Road Infrastructure Program - TRIP) - Brgy. Malubay to Brgy. Buong Lupa leading to Walang Langit Falls, Road Length= 1.037 lane km (516.5 L.M.) Pavement Width= 6.10m, Thickness= 0.23m thk. Construction of Retaining Wall Length= 236.89 m. See Plan and Details.
300203101214000	25EI0034 - Construction/ Improvement of Access Roads leading to Declared Tourism Destinations (Tourism Road Infrastructure Program - TRIP)- Internal Access Road to Sitio Palamang, Manihala leading to Manihala Waterfalls II, Bansud, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	20-Sep-24	10-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱9,800,000.00	₱9,800,000.00	Construction of Internal Access Road to Sitio Palamang, Manihala leading to Manihala Waterfalls II, Bansud, Oriental Mindoro, Road Length = 501.25m (1.1625 Lane KM ). Pavement Width = 6.10 m, Pavement Thickness = 0.23 m., Construction of Retaining Wall @ Right Side, 110m. Installation of 1 - Lines RCPC 1-0.60M. dia. x 9.00 M, Provide S-Type Headwall @ Both Side. See Plan and Details.
300203101656000	25EI0035 - Construction/Improvement of Access Roads leading Declared Tourism Destinations (Tourism Road Infrastructure Program - TRIP) - NRJ Leading to Phantom Cave and Bamboo Plantation, Gloria, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱9,800,000.00	₱9,800,000.00	Construction/Improvement of Access Roads leading Declared Tourism Destinations (Tourism Road Infrastructure Program - TRIP) - NRJ Leading to Phantom Cave and Bamboo Plantation, Road Length=1.18 lane km (588.58 L.M.) Pavement Width= 6.10m, Thickness=0.23m thk. Construction of Slope Protection @ First Section Left Side Length=60.0m, Construction of Retaining Wall @ Second Station Length=103.73m. See Plan and Details.
300214101957000	25EI0038 - Rehabilitation/Reconstruction/Upgrading of Damaged Paved Roads - Calapan South Road - K0117+000.00 - K0117+100.00, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱3,840,620.00	₱3,840,620.00	Rehabilitation/Reconstruction/Upgrading of Damaged Paved Roads - Calapan South Road - K0117+000.00 - K0117+100.00, Length = 0.200 Lane KM (100.00 L.M.), Construction of Open Lined Canal, 100.00 L.M. @ right side, Construction of Retaining wall 80.00 L.M. @ Left Side. See Plan and Details.
300214101958000	25EI0039 - Rehabilitation/Reconstruction/Upgrading of Damaged Paved Roads - Secondary Roads - Calapan South Road - K0166+006.00 - K0166+261.00, K0168+605.00 - K0168+1000.00, Mansalay-Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱13,195,700.00	₱13,195,700.00	Rehabilitation/Reconstruction/Upgrading of Damaged Paved Roads - Secondary Roads - Calapan South Road - K0166+006.00 - K0166+261.00, K0168+605.00 - K0168+1000.00, Road Length = 1.3000 Lane KM., Pavement Width = 3.05-3.35m., Pavement Thickness = 0.28 m., Gravel Shoulder @ Both Sides K0166+006-K0166+261= 1.30 m. Construction of Slope Protection @ Both Sides K0166+100-K0166+135, Extension of 1 Barrel 1.2m dia. RCPC @ K0166+097.40. See Plan and Details.
300214101959000	25EI0040 - Rehabilitation/Reconstruction/Upgrading Damaged Paved Roads - Secondary Roads along Calapan South Road - K0137+493.00- K0137+798.00, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	03-Oct-24	22-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱6,191,640.00	₱6,191,640.00	Rehabilitation/Reconstruction/Upgrading Damaged Paved Roads - Secondary Roads along Calapan South Road - K0137+493.00-K0137+798.00, Road Length= 305.00 L.M. (0.610 Lane K.M.), Carriageway Width= 6.70 m, Pavement Thickness= 0.28m., Construction of Open Lined Canal @ Both Sides, L=20.00 L.M., Installation of 1 Lined RCPC 0.91 dia. x 17.00m. See Plan and Details.
300214101954000	25EI0041 - Preventive Maintenance - Secondary Roads - Bongabong-Sagana-Roxas-Sn Aquilino Rd - K0105+574 - K0105+655, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	10-Sep-24	01-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱3,249,680.00	₱3,249,680.00	Preventive Maintenance - Secondary Roads - Bongabong-Sagana-Roxas-Sn Aquilino Rd - K0105+574 - K0105+655, Bongabong, Road Length = 0.1620 Lane KM., Pavement Width (Carriageway) = 6.10 m., Asphalt Thickness = 80 mm. See Plan and Details.



300214101960000	25EI0043 - Installation/Application of Road Safety Facilities (Roadway Lighting) along Calapan South Rd - K0067+226 - K0068+220, Pinamlayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	20-Sep-24	10-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱1,760,075.36		₱1,760,075.36	Installation of Single Arm 10m-Pole Solar LED Street Lighting (130 W) - 6 Units. See Plan and Details
300214101961000	25EI0044 - Installation/Application of Road Safety Facilities (Roadway Lighting) along Calapan South Rd - K0075+242 - K0076+238, Gloria-Pinamlayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱4,329,634.49		₱4,329,634.49	Installation of Single Arm 10m-Pole Solar LED Street Lighting (130W)-15 units. See Plan and Details
300214101962000	25EI0045 - Installation/Application of Road Safety Facilities (Roadway Lighting) along Calapan South Rd - K0072+721.00 - K0073+716.00, Pinamlayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	20-Sep-24	10-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱899,372.22		₱899,372.22	Installation of Single Arm 10m-Pole Solar LED Street Lighting (130 W) - 3 Units. See Plan and Details
300214101547000	25EI0046 - Improvement of Intersection at Calapan South Rd - K0140+000.00, Brgy. San Aguilino, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	29-Oct-24	19-Nov-24	13-May-25	23-May-25	GoP - Current Budget Year	₱14,700,000.00		₱14,700,000.00	Installation of Solar LED Roadway Lighting 24.00 pcs, Installation of Warning Signs - 4 pcs and Regulatory Signs - 18 pcs. Application of Pedestrian Lane Pavement Markings - 3 each. See Plan and Details.
300215107273000	25EI0051 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) - Construction of Road, Balatasan - Sitio Borbo Road, Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	03-Oct-24	22-Oct-24	28-Feb-25	11-Mar-25	GoP - Current Budget Year	₱44,550,000.00		₱44,550,000.00	Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) - Construction of Road, Balatasan - Sitio Borbo Road, Road Length = 3.867 lane km (1,833.50 L.M.), Pavement Width = 6.10 m. Thickness = 0.23m thk. Paving of Shoulder Bothside Thickness = 0.150m. Construction of Retaining Wall @ Left Side, Length = 377.5 m, Construction of Retaining Wall @ Right Side Length = 301.4 m. See Plan and Details.
300215107274000	25EI0052 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Road, Bagumbayan, NRJ-LTO, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	17-Sep-24	08-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱9,900,000.00		₱9,900,000.00	Construction of Road, Bagumbayan, NRJ-LTO, Roxas, Road Length = 0.7459 Lane KM, Pavement Width = 3.05 m., Pavement Thickness = 0.23 m., Concrete Shoulder Width @ Both Sides = 1.30 m., Pavement Thickness = 0.15 m., L = 43.00 L.M., Construction of Single Barrel Box Culvert 3.00m x 2.10m x 8.00m. Provide Wingwall and Apron @ Both Sides. Construction of Closed Lined Canal @ Right Side, L = 252.15 L.M., Installation of Solar LED Roadway Lighting 2.00 Pcs. See Plan and Details.
300215107276000	25EI0056 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Road at Sitio Sarada - Lagundi II, Barangay San Isidro, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	03-Oct-24	22-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱9,900,000.00		₱9,900,000.00	Construction of Road at Sitio Sarada - Lagundi II, Road Length = 618.0 L.M. (1.24 Lane km), Pavement Width = 6.10 m, Thickness = 0.23m thk, Shoulder Width = 1.0m bothside, Construction of Retaining Wall @ Second Station Length = 185.0 m., See Plan and Details.
300215107280000	25EI0061 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Road, Hagan-Sitio Panluan Road, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	20-Sep-24	10-Oct-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱19,800,000.00		₱19,800,000.00	Construction of Road, Hagan Sitio Panluan Road, Bongabong, Oriental Mindoro, Road Length=920.00m (1.840 Lane KM.) Pavement Width=5.00m, Pavement Thickness=0.23m, Construction of Double Barrel Box Culvert 3.00m x 6.90m x5.00m. Provide Wingwall and Apron @ Both Sides. Construction of Retaining Wall, L=570.00 L.M., See Plan and Details.
310202101962000	25EI0063 - Road Widening-Secondary Roads - Calapan South Rd - K0175+835 - K0176+215, Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱14,409,920.00		₱14,409,920.00	Road Widening-Secondary Roads - Calapan South Rd - K0175+835 - K0176+215, Length=0.684 lane km, Lane Width=3.35m, Pavement lane thickness=0.280 thk. Concrete Shoulder Width=2.0m @ Bothside. Construction of Slope Protection Length=40.0m @ Left Side. Construction of Covered Lined Canal Length=342.0 @ Right Side, 5.0 m @ Left Side, Extend of 1-0.90m x 3.0m @K0175+837.6m @ Bothside, 1-1.20m x 3.0 @ K0176+032.2 @ Right Side. Installation of 3.0 each Single Arm Solar LED Roadway Lighting (10.0m Pole) (125W - 150W). See Plan and Details.
300214101955000	25EI0064 - Preventive Maintenance - Secondary Roads - Along Calapan South Rd, K0131+467 - K0131+685, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱16,673,720.00		₱16,673,720.00	Preventive Maintenance - Secondary Roads - Calapan South Rd, K0131+467 - K0131+685, Bongabong, Road Length = 0.8720 Lane KM., Pavement Width (Carrageway) = 12.8 m., Asphalt Thickness = 80 mm. See Plan and Details.
300214101956000	25EI0065 - Preventive Maintenance - Secondary Roads - Along Calapan South Rd. K0153+000 - K0153+493, Mansalay, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱34,552,840.00		₱34,552,840.00	Preventive Maintenance - Secondary Roads - Calapan South Rd. K0153+000 - K0153+493, Mansalay, Road Length= 1.972 Lane KM., Pavement Width (Carrageway) = 12.2 m, Asphalt Thickness= 80 mm. See Plan and Details.
320101114028000	25EI0066 - Construction/Maintenance of Flood Mitigation Structures and Drainage Systems, Construction of Wasig River Control Structure, Barangay Wasig, Mansalay, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	27-Sep-24	17-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱29,400,000.00		₱29,400,000.00	Gabion Length = 154.00 L.M with closure at the beginning of the project. Construction of Pile Cap 0.60m x 0.70m and installation of Steel Sheet Piles, Length = 154.00 m. See Plan and Details.
300215107278000	25EI0067 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) - Construction of Road, Camundo - Tawas Road, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	29-Oct-24	19-Nov-24	28-Feb-25	07-Mar-25	GoP - Current Budget Year	₱9,900,000.00		₱9,900,000.00	Construction of Retaining Wall, L= 448.95 L.M. @ Left Side. Installation of 2 lines RCPC 1-0.61m dia. x 8.00m. Installation of 5 lines RCPC 1-0.91m dia. x 8.00m. See Plan and Details.
310202101961000	25EI0068 - Road Widening-Secondary Roads- Calapan South Rd - K0168+151 - K0168+345 K0173+366 - K0173+395, Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	29-Oct-24	19-Nov-24	28-Feb-25	10-Mar-25	GoP - Current Budget Year	₱7,184,380.00		₱7,184,380.00	Construction of Retaining Wall @ Left Side (First Section) Length= 97.0 L.M. Second Section @ Left Side Length= 14.0 L.M. Construction of Open Lined Canal @ Right Side (First Section Length= 194.0 L.M. Second Section Length=14.0 L.M. See Plan and Details.



300221106381000	25EI0070 - Construction of Road at Barangay Hagan, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	11-Nov-24	03-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of Road at Barangay Hagan, Bongabong, Oriental Mindoro, Road Length= 248.00 m (0.496 Lane KM), Pavement Width = 6.10m, Pavement Thickness = 0.23m, Shoulder Width = 1.00m, Construction of Retaining Wall, L= 175.70 L.M. @ Left Side. Installation of 1 lines RCPC 1-0.91m dia. x 8.00m. Provide S-Type Headwall Both Sides. See Plans and Details.
310202101803000	25EI0072 - Road Widening-Secondary Roads- Calapan South Rd - K0102 + 792.00 - K103 + 395.00, K0106 + 887.00 - K0107 + 000.00, K0108 + 502.00 - K0109 + 054.00, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	03-Oct-24	22-Oct-24	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱53,610,575.00	₱53,610,575.00	Road Widening-Secondary Roads- Calapan South Rd - K0102 + 792.00 - K103 + 395.00, K0106 + 887.00 - K0107 + 000.00, K0108 + 502.00 - K0109 + 054.00, Total Length 1,250.00 L.M. (2,500 Lane KM.), Pavement Width 3.35m, 0.28m thk. Construction of Retaining Wall with side walk @ Both sides, Total Length = 2,444.89 L.M. Extended RCPC 1-1.20m dia x 5.00m, Extended RCPC 2-0.910m dia x 8.00m, Extended RCPC 2-0.910m dia x 6.00m. 2 lined Extended RCPC 1-0.910m dia x 5800m. Installation of Solar LED Roadway Lighting 25.00 Pcs. See Plan and Details.
300215107275000	25EI0075 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Bridges, Libtong - Uyao Road, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	03-Oct-24	22-Oct-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱29,400,000.00	₱29,400,000.00	Construction of 286.20 sq.m. 2-RCDB Br., 2-Lanes, 1 span, 15.80 L.M. Br. Approach "A" & "B". PCPC Carriageway = 0.29840 Lane Km., 6.1m. wide, 0.28m. thk. Gravel shoulder = 0.29840 Lane Km., 2.00 m wide B/s. Construction of 248.40 L.M. Retaining wall with 16 sets Concrete Guardrails.
300226120804000	25EI0076 - Construction of Multi-Purpose Building (SK Building) at Barangay Poblacion, Mansalay, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	11-Nov-24	03-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of 1-unit two (2) storey Multi-Purpose building (SK Building) at Barangay Poblacion, Mansalay. This includes earthworks, reinforced concrete works, finishing and other civil works such as termite control works, such as termite control works, storm drainage and sewerage system, plumbing works, installation of ceilings, installation of steel doors and frames, aluminum glass door and windows, wooden doors, waterproofing, installation of glazed tiles and unglazed tiles, plastering, masonry painting, masonry works, installation of stainless railings (ramp) and electrical works.
300226120803000	25EI0077 - Construction of Multi-Purpose Building at Dangay National High School, Barangay Dangay, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	11 Nov 24	03 Dec 24	13 Mar 25	21 Mar 25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of a 1 unit Multi-Purpose building (Covered Court) measuring 18.00m x 30.00m, which includes embankment, reinforced concrete for column footings, column, footing tie beams, slab, beams, corbels, and gutters. The project also involves the fabrication and installation of trusses, roofing works, and downspout.
300226120795000	25EI0080 - Construction of Multi-Purpose Building at Barangay Nasucob, Bulalacao, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	11-Nov-24	03-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of 1 unit Multi-Purpose Building (Covered Court) measuring 18.00m x 30.00m, which includes embankment, reinforced concrete for column footings, column, footing tie beams, slab, beams, corbels, and gutters. The project also involves the fabrication and installation of trusses, roofing works, and downspouts.
300234100629000	25EI0089 - Construction of Drainage Canal at Sitio Bayanihan, Barangay Odiong, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	14-Nov-24	05-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of Drainage Canal at Sitio Bayanihan, Barangay Odiong, Roxas, Oriental Mindoro. Construction of Closed Lined Drainage including backfill at (Sta. 0+000.00 - Sta. 0+120.00). Construction of Lateral Box Culvert at (Sta. 0+120.00 - Sta 0+343.00). Drainage Length = 343.00 L.M. See Plan and Details.
300221106380000	25EI0099 - Construction of Road at Sitio Bintalan 1 & 2, Barangay San Jose, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	24-Jan-25	13-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of Road at Sitio Bintalan 1 and 2, Barangay San Jose, Bongabong, Oriental Mindoro, Road length = 349.00m (0.698 Lane K.M.), Pavement Width = 5 m, Pavement Thickness = 0.23 m. Construction of Retaining Wall @ Left Side 220.00 m. See Plan and Details.
300221106384000	25EI0100 - Construction of Road at Dimatulac St., Sitio Maligaya, San Aquilino, Roxas, Oriental Mindoro	Construction Section	No	Competitive Bidding	24-Jan-25	13-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of Road at Dimatulac St., Sitio Maligaya, Brgy. San Aquilino, Roxas, Oriental Mindoro, Road length = 376.00m (0.752 Lane KM.), Pavement Width = 5.00m, Pavement thickness = 0.23 m, Shoulder Width = 1.00 (max). Installation of 2 lines RCPC 1-0.91m dia. x 8.00m. Provide S-Type headwall Both Sides. See Plan and Details.
300234100630000	25EI0101 - Construction of Seawall at Barangay Aplaya, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	14-Nov-24	05-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱10,890,000.00	₱10,890,000.00	Construction of Seawall at Barangay Aplaya, Bongabong, Oriental Mindoro. Removal and Replacement of Existing Damaged Structure. Construction of 64.00 L.M. Seawall Revetment with Steel Sheet Piles (U-type) and Wave Deflector.
300226116986000	25EI0102 - Construction (Completion) of Multi-Purpose Building at Barangay Sabang, Pinamalayan, Oriental Mindoro, Phase II	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Completion of Covered Court, featuring a 2-tier steel bleacher system at both sides with a total length of 29.5 meters and the additional of a bay extending 2.8 meters. Scope of works includes earthworks, civil works, masonry works, surface preparation and painting of newly installed existing beams and columns, steel painting of rafters and purlins for the bleacher structure, as well as complete flashing and roofing installation.

300226116983000	25EI0103 - Construction (Completion) of Multi-Purpose Building at Barangay Buli, Pinamalayan, Oriental Mindoro, Phase II	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(16m x 30m) Phase II. This includes installation of end-wall cover at front and rear side, construction of concrete bleachers at right side (18.40 m), installation of steel matting, plastering, masonry and steel painting, installation of basketball goal post, construction of concrete canal at front and right side with steel grating cover and electrical works including installation of high bay lights and score board.
300226120820000	25EI0104 - Construction(Completion) of Multi-Purpose Building at Barangay Bonbon, Mansalay, Oriental Mindoro, Phase II	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(18 m x 30 m), Phase II. This includes construction of 5 meters additional bay, construction of stage, installation of end wall cover at left and right side, plastering, masonry and steel painting, installation of basketball goal post and electrical works including installation of high-bay lights.
300226120794000	25EI0105 - Construction of Multi-Purpose Building (Evacuation Center) at Barangay Pili, Pinamalayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of Multi-Purpose Building (Evacuation Center). This include earthworks, civil works, masonry painting (painting of perimeter walls, beams and column), steel painting (painting of steel trusses, purlins and railings), roofing works, and plumbing works (sewer lines, cold water lines, septic tank and plumbing fixtures).
300226120800000	25EI0106 - Construction(Completion) of Multi-Purpose Building at Barangay Ipil, Bongabong, Oriental Mindoro, Phase II	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Completion of One unit Two-Storey Multi-Purpose Building, Barangay Hall (2-10.2m x 7.85m). This includes the installation of floor tile at ground and second floor, complete ceiling system for ground and second floor, stainless steel signage and logo at front exterior wall and additional tubular pipes for grills. Works also includes carpentry and joinery works, decorative stone, masonry and concrete painting for interior and exterior areas, ceiling painting at ground and second floors, steel painting for grills. It also includes installation of mechanical and electrical works.
300226120807000	25EI0107 - Rehabilitation of Multi-Purpose Building at Brgy. Panggulayan, Pinamalayan, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Completion of 1- unit Multi-Purpose Building (Covered Court) with dimension of 18.07m x 30.00m, including structural and finishing works. Scope includes site preparation, earthworks, cement plastering, and masonry painting for both newly installed and existing beams, columns, and bleachers. Rubberized floor painting, along with demolition and replacement of existing slab sections and the removal of an existing basketball post. Additionally, it includes 1-bay extension, extension of concrete gutter, construction of 21.20, length painted concrete-finished bleacher on the rear side. Installation of trusses, purlins, gutter, flashing, end-wall side flashing, steel matting, catch basins, downspouts, & electrical works are also included.
300226116982000	25EI0108 - Construction (Completion) of Multi-Purpose Building at Barangay Sta. Isabel, Pinamalayan, Oriental Mindoro, Phase II	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(16 m X 30 m) Phase II. This include installation of endwall, cover at front and rear side, construction of steel bleachers at left & right side (56.5 m), installation of steel matting fence at front and right side, plastering, masonry and steel painting, application of rubberized paint flooring, installation of basketball goal and electrical works including installation of high bay lights and score board.
300226120822000	25EI0109 - Construction of Multi-Purpose Building (Covered Court) at Balugo National High School, Barangay Balugo, Mansalay, Oriental Mindoro, Phase II	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Completion of 1-unit Multi-Purpose Building (Covered Court) 17.0m x 32.8m. This includes earthworks, concreting of slab, cement plastering & masonry painting (existing beams and columns), completing of steel trusses and purlins, removal and replacement of existing roof metal sheets and removal of concrete. Additionally, this project includes 6 sets of movable steel bleachers, installation of pre-painted metal sheet, gutter, flashing, end wall cover at front and rear side, downspout, catch basin, electrical works, steel painting of trusses, purline and movable bleacher.



300226120779000	25EI0110 - Construction of Facilities for Persons with Disabilities (PWD) and Elderies/ Senior Citizens including Gender I Responsible Facilities Phase II, San Mariano, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱19,800,000.00		₱19,800,000.00	Construction of Facilities for Persons with Disabilities (PWD) and Elderies/ Senior Citizens including Gender I Responsible Facilities (16.5m x 36.25m) Phase II. This includes earthworks, reinforced concrete works and finishing and other civil works such as soil poisoning, installation and construction of storm drainage and sewerage system (Note: For Second Floor and Roof Deck; plumbing roughing-ins only), installation of plumbing fixtures and ground floor to roofdeck, waterproofing, installation of floor and wall tiles and ground floor, plastering & masonry painting at ground floor & multi-purpose hall, painting of ceiling and wood doors, installation of reflective, insulation, roofing works, installation of ramp railings and glass railings. Moreover, this includes electrical works (Note: For Second Floor and Roof deck, electrical roughing-ins only) and provision of fire extinguisher at ground floor.
300226120823000	25EI0111 - Construction(Completion) of Multi-Purpose Building (Covered Court) at Barangay Batangan, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	21-Nov-24	12-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(15 m x 28 m) at Brgy. Batangan, Bongabong. This includes earthworks, reinforced concrete works, installation of precast end flashing, installation of precast metal sheets, & installation of steel plates, truss, purlins, sagrods, turnbuckle, and cross bracing.
300226120811000	25EI0112 - Construction (Completion) of Multi-Purpose Building at Barangay Cawayan, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of 1-unit Multi-Purpose Building (Barangay Hall) at Barangay Cawayan, Phase II. This includes the installation of floor tiles at ground and second floors, waterproofing (built-up and preformed membrane) at the roof deck, complete ceiling systems for ground and second floors, stainless steel signage at front exterior wall, and additional G.I. Pipes and square steel bars for railings. Works also include masonry and concrete painting for interior and exterior areas, ceiling painting at ground and second floors, steel painting of existing square bar railings, and fabrication and installation of stainless steel railings at roof deck, and flat form at session hall.
300226120805000	25EI0113 - Construction (Completion) of Multi-Purpose Building at Barangay Masaguisi, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Barangay Hall) at Barangay Masaguisi, Phase II. This includes installation of floor tiles with waterproofing (built-up and preformed membrane) at roof deck, drop ceilings on ground and second floor, indoor wall cladding, polystyrene baseboards, outdoor cladding at front and right elevations, decorative stone at roof deck, and stainless signages on exterior front wall. Also includes painting of roof deck columns, ceilings, steel railings, and fabrication/installation of new steel railings at roof deck, and flat form at session hall.
300226120813000	25EI0114 - Construction (Completion) of Multi Purpose Building at Barangay San Isidro, Roxas, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit- 2-Storey Multi Purpose Building at Barangay San Isidro. This includes earthworks, demolition of existing obstruction structure, structural reinforced concrete works, plastering works, railings, tile works, finishing works, painting works, roofing works, plumbing, electrical works and other mechanical works.
300226120801000	25EI0115 - Construction (Completion) of Multi-Purpose Building at Barangay Aplaya, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose building (Covered Court) at Aplaya, Phase II. This includes installation of end wall flashing at front and rear, construction of concrete bleachers at left side, plastering, painting works, storm drainage and sewerage system, roofing works. Installation of basketball ring, installation of flashing and gutter, installation of welded wire fencing and electrical works including installation of scoreboard.
300226120799000	25EI0116 - Construction (Completion) of Multi-Purpose Building at Barangay Malo, Bansud, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of Covered Court, featuring a 2-tier bleacher system at the rear elevation with a total length of 30.00 meters, and the addition of a bay extending 5.10 meters. Scope of work includes comprehensive earthworks, civil works, masonry works, surface preparation and painting of newly installed existing beams, columns, and bleachers, steel painting of rafters and purlins for the bleacher structure, as well as complete roofing installation, fabrication and installation of backboard/ring/frame.
300226120806000	25EI0117 - Construction (Completion) of Multi-Purpose Building at Barangay Mapang, Phase II, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit 2-Storey Multi-Purpose Building with dimensions 12.3m x 6.4m. The project includes earthworks, structural works, and the extension of the second floor, along with concrete finishing and wall painting for new structures and demolition. It also involves tile installation (including interior floors on the second floor and stair) and roof installation, including rafters, purlins, gutters, flashing and downspouts. Additionally, the scope includes installation of ceiling, doors and windows, decorative stonework, tower blocks, electrical works and mechanical works.

300226120810000	25EI0118 - Construction (Completion) of Multi Purpose Building at Barangay San Isidro, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of Covered Court, featuring 3-tier steel bleacher system at both sides with a total length of 30 meters and the additional of a bay extending 5 meters. Scope or works includes installation of basketballboard and ring, earthworks, civil works, masonry works and electrical works, surface preparation and painting of newly installed existing beams and columns, steel painting of rafters and purlins for the bleacher structure, as well as complete flashing and roofing installation.
300226116984000	25EI0119 - Construction (Completion) of Multi-Purpose Building at Barangay Banilad, Pinamalayan, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of Covered Court (Construction of 2-Tier Bleacher, 28.84 meters in length). This includes earthworks, civil works, masonry painting (painting of existing beams and column, and bleachers), steel painting (painting of rafters and purlins of bleachers), roofing works, installation of a basketball ring and Steel Matting Fence (21.20 meters in length and 4.70 meters high at front elevation), & (14.70 meters in length and 4.00 meters high on the left side).
300226120797000	25EI0120 - Construction (Completion) of Multi-Purpose Building at Barangay Pambisan Munti, Pinamalayan, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of Covered Court (Construction of 3-Tier Bleacher, 30.03 meters in length at left side) & (Construction of 2-Tier Bleacher, 30.03 meters in length at right side). This includes earthworks, civil works, masonry painting (painting of existing beams and column, and bleachers), steel painting (painting of rafters and purlins of bleachers) and roofing works, installation of steel matting at rear elevation of both bleachers, fabrication and installation of background/ring/frame.
300226120819000	25EI0121 - Construction (Completion) of Multi-Purpose Building (ALS Building) at Barangay Victoria, Roxas, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of 1-Unit Multi-Purpose Building. This includes cement plaster finish, Masonry painting, tile works, it is also includes installation of doors and windows carpentry works, electrical, mechanical works and plumbing fixtures.
300226120809000	25EI0122 - Construction (Completion) of Multi-Purpose Building at Barangay Lisap, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of 1-unit Multi-Purpose Building. This includes additional concrete works (moulding of windows & kitchen countertop), paintings, ceiling works, tile works, septic tank, cistern, water pumping system, electrical & mechanical works. Installation of stainless steel signages, decorative stone, railing, fire escape ladder, plumbing fixtures, windows, kitchen cabinet, downspout, catch basin, sewer lines, cold water lines, and replacement of gutter are also included.
300226120815000	25EI0123 - Construction (Completion) of Multi-Purpose Building at Barangay Cagugao, Bulalacao, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	27-Dec-24	16-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(16 m x 30 m) at Brgy. Cagugao, Bulalacao, Phase II. This includes construction of 2-layered concrete bleachers (30.1 m) at front side with roofing, installation of end wall cover at left and right side, construction of sidewalks at rear and left side, installation of steel matting fence at all sides, plastering, masonry and steel painting, installation of basketball goal post and electrical works including installation of high-bay lights and scoreboard.
300226120812000	25EI0124 - Construction (Completion) of Multi Purpose Building at Barangay Luna, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court) at Luna, Phase II. This includes installation of end wall flashing at front and rear and construction of concrete bleachers at left side. This also includes plastering, painting works, roofing works. Lastly, this project includes, installation of basketball ring, installation of flashing and gutter and electrical works including installation of scoreboard.
300226120817000	25EI0125 - Construction (Completion) of Multi Purpose Building at Barangay Benli, Bulalacao, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(18mx30m) at Benli, Phase II. This includes installation of end wall flashing at front and rear and construction of concrete bleachers (30.4m) at left side. Moreover, this also includes plastering, painting works, roofing works. Lastly, this project includes installation of unglazed tiles (bleachers), installation of basketball ring, installation of flashing and gutter and electrical works including installation of scoreboard.
300226116985000	25EI0126 - Construction (Completion) of Multi-Purpose Building at Barangay San Vicente, Roxas, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	The scope of works includes the construction of bleachers on the both sides of the covered court, with the right side having 3 layers and the left side 5 layers both 30 meters long. This also includes excavation works, reinforced concrete for column footing, and slabs, as well as finishing works such as CHB laying, plastering and wall painting. Additionally, it covers the fabrication and installation of rafters, struts, purlins, frames, roofing and installation of basketballboard and ring.



300226120818000	25EI0127 - Construction (Completion) of Multi Purpose Building (Covered Court) at Barangay Victoria, Roxas, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Completion of Covered Court, featuring 3-tier movable steel bleacher with a total length of 7.56 meters and additional of a bay extending 4.65 meters. Scope of works includes earthworks, civil works and electrical works, surface preparation and painting of newly installed beams and columns. It includes additional toilet room for men and women, masonry works, tile works and painting for masonry and steel such as rafters and purlins for the bleachers structure, installation of end wall flashing, flashing, gutter and roofing works.
300226120825000	25EI0128 - Construction (Completion) of Multi Purpose Building (Covered Court) at Barangay San Miguel, Roxas, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Construction 1- unit Multi-Purpose Building (Covered Court) at San Miguel, Phase II. This includes installation of end wall flashing at left and right side, construction of concrete bleachers with roofing at rear side, construction of comfort rooms, installation of floor & wall tiles, installation of plumbing fixtures, and plastering of beams columns, corbel and bleachers. Additionally, this project includes installation of basketball ring, installation of flashing and gutter and electrical works including installation of scoreboard.
300226120816000	25EI0129 - Construction (Completion) of Multi Purpose Building at Barangay San Isidro, Bulalacao, Oriental Mindoro	Construction Section	No	Competitive Bidding	03-Jan-25	23-Jan-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Construction of a- 1 unit Multi-Purpose Building (Day Care Center) measuring 9.80m x 8.20m, which includes excavation, embankment, reinforced concrete for column footings, column, footing to beams, slab, beams, and suspended slab. The project also involves the fabrication and installation of trusses, roofing works, plumbing works, and downspouts. Also includes painting works, tileworks of CR, electrical works, ceiling works, blackboard, and other finishing works to complete the project.
300226120821000	25EI0130 - Construction (Completion) of Multi-Purpose Building at Tomas S. Villanueva Memorial School, Barangay Sagana, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	15-Jan-25	04-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Construction of 1 unit - Multi-Purpose Building (Covered Court)(14m x 25m) at Tomas S. Villanueva Memorial School, Brgy. Sagana, Bongabong. This includes earthworks, removal of existing structures, reinforced concrete works, installation of pre-painted end flashing, installation of pre-painted metal sheets, & installation of steel plates, truss, purlins, sagrods, turnbuckle, and cross bracing.
300226120793000	25EI0131 - Construction of Multi-Purpose Building (Health Center) at Barangay Rosario, Pinamalayan, Oriental Mindoro	Construction Section	No	Competitive Bidding	15-Jan-25	04-Feb-25	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of Multi-Purpose Building (Health Center). This includes earthworks, civil works, masonry painting (painting of perimeter walls, beams and column), steel painting (painting of Railings, plumbing works (sewer lines, cold water lines, septic tank and plumbing fixtures), electrical works (wires and wiring devices, conduits boxes and fittings, panel board, and lighting fixtures), and mechanical works (fire extinguisher and fire alarm system).
300226116987000	25EI0132 - Rehabilitation (Completion) of Regional Trial Court, Roxas, Oriental Mindoro	Construction Section	No	Competitive Bidding	15-Jan-25	04-Feb-25	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Rehabilitation of Regional Trial Court, (Extension at right side elevation and rear elevation). This includes earthworks, civil works, masonry painting (painting of perimeter walls, partition walls, beams and column), steel painting (painting of steel trusses, purlins and railings), roofing works, and plumbing works (sewer lines, cold water lines, septic tank and plumbing fixtures).
300226120824000	25EI0133 - Construction (Completion) of Multi-Purpose Building (Covered Court) at Barangay Libertad, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	15-Jan-25	04-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(16mx30m), Phase II. This includes removal of existing slab, construction of intermediate beams & columns left and right side, concreting of slab on fill, construction of 2 layered steel bleachers (26.2m) at front side, installation of end wall cover at left and right side, plastering, masonry and steel painting, rubberized floor painting, installation of basketball goal post and electrical works including installation of high-bay lights and scoreboard.
300226120814000	25EI0134 - Construction (Completion) of Multi-Purpose Building at Barangay B. Del Mundo, Mansalay, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	15-Jan-25	04-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Completion of 1 unit Multi- Purpose Building. The scope of works includes complete masonry painting to the exterior walls of the building, complete interior painting of ground floor walls and exposed slab ceiling, complete cement plastering on all walls throughout the building, installation of ceiling systems on the second floor, toilet and stage, installation of tile works on ground floor and stairs. Electrical and mechanical works, construction of additional wall and extension of wall on stage, remove and replace of ceiling at BDRMO and installation of doors, windows, and plumbing fixtures are also included.



300226120792000	25EI0135 - Construction of Multi-Purpose Building (ABC Building), Pinamalayan, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	15-Jan-25	04-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Construction of 1-unit Multi Purpose Building (ABC Building) at Pinamalayan, Phase II. This includes removal of chb wall partition at ground floor, installation of ceiling at roofdeck level, installation of cabinets (pantry), installation of WPC wall panel, installation of swing door at ground floor, installation of fixed window at ground floor, waterproofing, installation of glazed & unglazed tiles at roofdeck level, installation of airconditioning system, and installation of AFSS System.
300226120808000	25EI0136 - Construction of Multi-Purpose Building at Barangay Cantil, Roxas, Oriental Mindoro	Construction Section	No	Competitive Bidding	15-Jan-25	04-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Construction of Multi-Purpose Building (Barangay Hall). This includes earthworks, civil works, masonry painting (painting of perimeter walls, beams and column), steel painting (painting of steel trusses, purins and railings), roofing works, fabrication and installation of stainless steel signage, decorative stone, air conditioning of (barangay captain's office and session hall), and plumbing works (sewer line, cold water lines, septic tank and plumbing fixtures).
300215107283000	25EI0137 - Construction (Completion) of Road at Barangay Bagong Bayan II, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	17-Jan-25	06-Feb-25	25-Mar-25	04-Apr-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction (Completion) of Road at Barangay Bagong Bayan II, Bongabong, Oriental Mindoro, Road Length = 199.10m (0.3982 Lane KM.). Pavement width = 5.00m, Pavement Thickness = 0.23 m, Shoulder Width = 1.00m. Application of Reflectorized Thermoplastic Pavement Markings (White) 119.46 sq.m.
300215107285000	25EI0138 - Construction (Completion) of Road at Barangay Bacungan, Pinamalayan, Oriental Mindoro	Construction Section	No	Competitive Bidding	17-Jan-25	06-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱3,960,000.00		₱3,960,000.00	Construction of Road at Barangay Bacungan, Pinamalayan, Oriental Mindoro, Road Length = 0.5900 Lane KM., Carriage Way Width = 5.0 m, Pavement Thickness = 0.23 m, Gravel Shoulder Width @ Both Sides- 1.0 m., Construction of Single Barrel Reinforced Concrete Pipe Culvert 0.6m. Dia., Length = 8.00m. See Plan and Details
300234100528000	25EI0139 - Construction (Completion) of Slope Protection at Barangay Sta Cruz, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	17-Jan-25	06-Feb-25	25-Mar-25	04-Apr-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction (Completion) of Slope Protection at Barangay Sta. Cruz, Bongabong, Oriental Mindoro, Length= 48.00 L.M. . Construction of 1-Layer Slope Protection, Height = 4.00 m, with Closure at the beginning and end of the project. See Plan and Details.
300234100631000	25EI0140 - Construction (Completion) of Drainage Canal at Facoma St., Barangay Bagong Bayan II, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	17-Jan-25	06-Feb-25	25-Mar-25	04-Apr-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of Drainage Canal at Facoma St., Barangay Bagong Bayan II, Bongabong, Oriental Mindoro. Construction of Closed Lined Drainage including backfill. Drainage length = 312.00 L.M. See plan and details.
300234100632000	25EI0141 - Construction (Completion) of Drainage Canal at Sitio Asiatic, Barangay Ipil, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	17-Jan-25	06-Feb-25	25-Mar-25	04-Apr-25	GoP - Current Budget Year	₱3,960,000.00		₱3,960,000.00	Construction of Drainage Canal at Sitio Asiatic, Barangay Ipil, Bongabong, Oriental Mindoro. Construction of Closed Lined Drainage including backfill. Drainage Length = 348.00 L.M. See Plans and Details.
310111100844000	25EI0142 - Construction/ Upgrading/ Rehabilitation of Drainage along National Roads - Secondary Roads - Calapan South Rd-K0078+363.00 - K0078+467.00, K0082+830.00- K0083+029.00, K0093+113.00-K0093+151.00, Gloria, Oriental Mindoro	Construction Section	No	Competitive Bidding	22-Jan-25	11-Feb-25	07-Aug-25	15-Aug-25	GoP - Current Budget Year	₱7,856,660.00		₱7,856,660.00	Covered Drainage Length = 616.00 L.M., Covered Drainage Width = 1.50 m, outer/ 1.20 m inner. See Plan and Details.
300215107272000	25EI0143 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Road, Marayos - Sabang, Pinamalayan, Oriental Mindoro	Construction Section	No	Competitive Bidding	22-Jan-25	11-Feb-25	25-Mar-25	04-Apr-25	GoP - Current Budget Year	₱14,850,000.00		₱14,850,000.00	Construction of Road, Marayos-Sabang, Pinamalayan, Oriental Mindoro, Road Length=762.00 (1.5240 Lane KM.), Pavement Width=6.10 m., Pavement Thickness=0.23 m., Installation of 2 Line-RCPC-1.20m dia x 9.0m. Provide S-Type Headwall @ Bothside. Construction of Retaining Wall, L=587.5 L.M., See Plan and Details.
300215107279000	25EI0144 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction (Completion) of Road, Sitio Alejandra - Labasan Road, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	22-Jan-25	11-Feb-25	25-Mar-25	04-Apr-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) Construction (Completion) of Road, Sitio Alejandra-Labasan Road, Bongabong, Oriental Mindoro, Road Length=168.30m (0.3366 Lane K.M.), Pavement Width = 5.00m., Pavement Thickness = 0.23 m., Shoulder Width = 0.50 m, Construction of Retaining wall @ B/S, 203.1m. Installation of 1-Lined RCPC 1-0.60M. dia x 9.00 M, Provide S-type Headwall @ Both Side. See plan and details.
300226116981000	25EI0145 - Construction of Multi-Purpose Building at DPWH Compound, San Mariano, Roxas, Oriental Mindoro	Construction Section	No	Competitive Bidding	22-Jan-25	11-Feb-25	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱33,418,440.00		₱33,418,440.00	Construction of Multi-Purpose Building at DPWH Compound, San Mariano, Roxas, Oriental Mindoro. This includes earthworks, reinforced concrete works and finishing and other civil works such as soil poisoning, installation and construction of storm drainage and sewerage system, installation of plumbing fixtures at ground floor and mezzanine, installation of ceiling at ground floor, mezzanine, and multi-purpose hall, installation of doors and windows, waterproofing, installation of floor and wall tiles at ground floor, plastering & masonry painting at ground floor & multi-purpose hall, painting of ceiling and wood doors, installation of reflective, insulation, roofing works, installation of ramp railings and glass railings. Moreover, this includes electrical works and provision of fire extinguisher at ground floor.



300226120796000	25EI0146 - Construction of Poblacion Multi Purpose Building at Barangay Poblacion, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	22-Jan-25	11-Feb-25	25-Mar-25	04-Apr-25	GoP - Current Budget Year	₱7,920,000.00	₱7,920,000.00	Construction of 1-unit Multi-Purpose Building (Membrane Structure) (30 m x 50 m), Phase II. This includes earthworks, concreting of slab, installation of steel structures and accessories, plastering, masonry painting and steel painting.
300226120798000	25EI0147 - Construction of Multi-Purpose Building at Barangay San Antonio, Gloria, Oriental Mindoro	Construction Section	No	Competitive Bidding	22-Jan-25	11-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of 1-Unit Senior Citizen Building. Complete construction of 1 Unit 1-Storey Senior Citizen Building with dimensions 10.8m x 15.3m. The project includes concrete works, plastering works, tile installation, ceiling works, roofing works, railings, painting works (masonry & steel), sanitary works such as installation of plumbing fixtures, cold water lines, power lines, cath basin, septic tank, and downspout. Installation of doors and windows, installation of decorative stone with stainless steel signages, mechanical (pressurized water tank, fire protection system & air conditioning system) and electrical works are also included.
300215107284000	25EI0148 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Road at Dimatula St. Sitio Maligaya, San Aquilino, Roxas, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	14-Nov-24	05-Dec-24	24-Mar-25	04-Apr-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) Construction of Road at Dimatula St. Sitio Maligaya, San Aquilino, Roxas, Oriental Mindoro, Road Length= 214.00m(0.4280 Lane Km.), Pavement Width = 5.00 m, Pavement Thickness = 0.23m., Shoulder Width = 1.00m, Installation of Solar LED Roadway Lighting 7.00 Pcs. See Plan Details.
300215107281000	25EI0149 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Road at Sitio Bintalan 1 and 2, Barangay San Jose, Bongabong, Oriental Mindoro	Construction Section	Yes	Competitive Bidding	14-Nov-24	05-Dec-24	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) Construction of Road at Sitio Bintalan 1 & 2, Barangay San Jose, Bongabong, Oriental Mindoro, Road Length = 410.00m (0.820 KM Lane). Pavement Width = 5m, Pavement Thickness = 0.23 m, Shoulder Width = 0.50 m. Construction of Retaining Wall @ Right Side 30.00 m. See Plan and Details.
300221108379000	25EI0150 - Construction of Bridge, Brgy. Cambunang, Bulalacao, Oriental Mindoro	Construction Section	No	Competitive Bidding	24-Jan-25	13-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱18,810,000.00	₱18,810,000.00	Construction of 190.80 sq m. 1-PCDG Br., 2-Lanes, 1 span, 20.00 L.M. Br. Gravel Carriageway = 0.14000 Lane Km., 6.10 m wide, Gravel Shoulder=0.1400 Lane Km., 2.00 m wide B/S. Construction of 80.00 L.M. Retaining Wall with 8 sets Concrete Guardrails.
300226120826000	25EI0152 - Construction of Multi-Purpose Facility (Covered Court), Aplaya Elementary School, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	24-Jan-25	13-Feb-25	13-May-25	23-May-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of a 1 unit Multi-Purpose Building (Covered Court) measuring 18.00m x 30.00m, which includes embankment, reinforced concrete for column footings, column, footing tie beams, slab, corbels, and gutters. The project also involves the fabrication and installation of trusses, roofing works, and downspouts.
300226120780000	25EI0153 - Completion (Construction) of Multi Purpose Building (Barangay Hall) at Brgy. Carmundo, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	24-Jan-25	13-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Completion of 1-unit Multi-Purpose Building (Barangay Hall) at Barangay Carmundo. This includes the installation of floor tiles at ground and second floors, waterproofing (built-up and preformed membrane) at the roof deck, complete ceiling systems for ground and second floors, stainless steel signage at front exterior wall, and additional GI pipes and square steel bars for railings. Works also include masonry and concrete painting for interior and exterior areas, ceiling painting at ground and second floors, steel painting existing square bar railings, and fabrication and installation of stainless steel railings at roof deck, flat form at season hall, and installation of three(3) air condition units.
300226120790000	25EI0154 - Completion of Multi-Purpose Building at Barangay Luna, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	24-Jan-25	13-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00	₱2,970,000.00	Completion of 1-unit Multi-Purpose (Covered Court) at Luna. This includes construction of bleacher at front side, construction of stage with common comfort room, installation of wood paneled door and PVC door, installation of plumbing fixtures, plumbing works, plastering, painting works, roofing works, and construction of steel grating canal at right side.
300215107282000	25EI0155 - Construction of Road at Barangay Hagan, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	05-Feb-25	25-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱6,930,000.00	₱6,930,000.00	Construction of Road at Barangay Hagan, Bongabong, Oriental Mindoro. Road Length=394.00m (0.788 Lane Km.), Pavement Width = 5.00m., Pavement Thickness=0.23m., Shoulder width=1.00m. Installation of 1 lines RCPC 1.0.91m dia x 8.00m. Provide S-Type Headwall Both Sides. See plan and details.
300226120830000	25EI0156 - Construction of Multi-Purpose Building, Barangay Sagana, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	24-Jan-25	13-Feb-25	07-Aug-25	15-Aug-25	GoP - Current Budget Year	₱4,950,000.00	₱4,950,000.00	Construction of 1-Multi-Purpose Building (Stage and Bleachers) at Barangay Sagana. This includes construction of bleacher with canopy roof at left side construction of stage and additional one-bay of covered court, installation of basketball board/ring, plastering, masonry and steel painting, and installation of storm and drainage system.
300215105605000	25EI0157 - Construction of Army Camp Road, Bansud, Oriental Mindoro	Construction Section	No	Competitive Bidding	28-Jan-25	18-Feb-25	13-May-25	23-May-25	GoP - Current Budget Year	₱49,500,000.00	₱49,500,000.00	Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) - Construction of Army Camp Road, Bansud, Oriental Mindoro. Road Length = 2,500.00m(5.000 Lane Km.), Pavement Width = 6.10 m., Pavement Thickness = 0.23 m., Shoulder Width = 1.00m. Installation of 10 lines RCPC 1.0.91m dia. x 9.00m. Provide S-Type Headwall Both Sides. See Plan and Details.



300215107277000	25EI0158 - Sustainable Infrastructure Projects Alleviating Gaps (SIPAG)-Construction of Road, Ogbot-Dayhagan Road, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	28-Jan-25	18-Feb-25	21-Mar-25	28-Mar-25	GoP - Current Budget Year	₱19,800,000.00		₱19,800,000.00	Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) Construction of Road, Ogbot-Dayhagan Road, Bongabong, Oriental Mindoro. Road Length = 681.00m (1.362 Lane KM), Pavement Width = 6.10m, Pavement Thickness = 0.23m, Shoulder Width = 1.00m. Installation of 5 lines RCPC 1-0.91m dia. x 9.00m. Provide S-type Headwall Both Sides. See Plan and Details.
300221108378000	25EI0159 - Construction of Road, Sitio Payong, Brgy. Orconuma, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	05-Feb-25	25-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Construction of Road, Sitio Payong, Brgy. Orconuma, Bongabong, Oriental Mindoro. Road Length=328.25m (0.6565 Lane KM), Pavement Width = 5 m., Pavement Thickness=0.23m., Shoulder width=0.50 m. Construction of Retaining Wall 379.70m. Installation of 4 lines RCPC 1-0.61m dia. x 7.00m. Provide S-Type Headwall Both Sides. See Plan and Details.
300221108382000	25EI0160 - Rehabilitation of Road, Brgy. Rosacara, Bansud, Oriental Mindoro	Construction Section	No	Competitive Bidding	28-Jan-25	18-Feb-25	07-Aug-25	15-Aug-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Rehabilitation of Road at Brgy. Rosacara, Bansud, Oriental Mindoro. Road Length = 300.00m(0.600 Lane KM.), Pavement Width = 5.00 m., Pavement Thickness = 0.23 m., Shoulder Width = 1.00m. See Plan and Details.
300221108383000	25EI0161 - Construction of Road, Brgy. Cawayan to Brgy. Camantique, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	05-Feb-25	25-Feb-25	07-Aug-25	15-Aug-25	GoP - Current Budget Year	₱49,500,000.00		₱49,500,000.00	Construction of Road, Brgy. Camantique, Bongabong, Oriental Mindoro. Road Length=2,500.00m (5.000 Lane KM.), Pavement Width = 6.10m, Pavement Thickness=0.23m., Shoulder width=0.50 m. Installation of 10 lines RCPC 1 0.91m dia x 9.00m. Provide S-Type Headwall Both Sides. See plan and details.
300228100664000	25EI0162 - Construction of Oriental Mindoro Central District Hospital, Pinamalayan, Oriental Mindoro	Construction Section	No	Competitive Bidding	21-May-25	10-Jun-25	01-Jul-25	11-Jul-25	GoP - Current Budget Year	₱64,350,000.00		₱64,350,000.00	Completion of Central Hospital, Construction of Two (2) Additional Floor (Second and Third Floor). This includes earthworks at (drop off and concrete louvers), civil works, masonry painting (painting of perimeter walls, beams and column), wood painting (painting of wood panel door and flush door), steel painting (painting of steel trusses, and purlines), roofing works, fabrication and installation of stainless steel signage and railings, air conditioning unit (7 sets-3/4 HP split type, 7 sets-1 HP split type, 2 sets-1.5HP split type, 10 sets-2HP split type), Fire Protection (fire alarm system, sprinkler lines, and fire extinguisher) and plumbing works (sewer lines, cold water lines, storm drainage and downspout, catch basin, and plumbing fixtures).
300226120781000	25EI0163 - Completion (Construction) of Multi Purpose Building at Brgy. Papandungin, Gloria, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	28-Jan-25	18-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of Covered Court (Construction of Stage at Rear Elevation), and Installation of End Wall Flashing. This includes earthworks, civil works, masonry painting (painting of existing beams & column), steel painting (painting of rafters and purlines of bleachers), roofing works, and Steel Matting Fence (21.73 meters in length and 3.0 meters high at front elevation), & (14.76 meters in length and 4.65 meters high at left side).
300226120782000	25EI0164 - Completion (Construction) of Multi Purpose Building at Brgy. Anoling, Pinamalayan, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	31-Jan-25	20-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit 1-Storey Multi-Purpose Building (SK Building Office). It includes structural works, roofing works, plumbing works, electrical works and installation of doors and windows.
300226120783000	25EI0165 - Completion (Construction) of Multi Purpose Building at Brgy. Palayan, Pinamalayan, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	28-Jan-25	18-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of 1-Unit 2-Storey Evacuation Center (10.5m x 11.5m). This includes construction of slab, dirty kitchen, & plant box and remove and relocation of kitchen sink. This also includes finishing works such as plastering, painting (masonry, steel, & wood), installation of painted ceiling at ground floor level, tile works, installation of cabinet, stainless steel signage at the front side of wall, electrical works and mechanical works.
300226120784000	25EI0166 - Completion (Construction) of Multi Purpose (Covered Court) at Brgy. Odiong, Roxas, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	05-Feb-25	25-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of 1-unit Multi-Purpose Building (Covered Court)(18m x 30m) Phase II. This includes installation of endwall cover at front and rear side, construction of steel bleachers at left & right side (56.5m), installation of steel matting fence at front and right side, plastering, masonry and steel painting, application of rubberized paint flooring, installation of basketball goal post and electrical works including installation of high bay lights and score board.
300226120785000	25EI0167 - Completion (Construction) of Multi Purpose Building (Covered Court) at Brgy. Hagupit, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	05-Feb-25	25-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(18m x 30m) Phase II. This includes construction of 5 meters additional bay, construction of stage, installation of endwall cover at left and right, plastering, masonry and steel painting, installation of basketball goal post and electrical works including installation of high bay lights.



300226120786000	25EI0168 - Completion (Construction) of Multi-Purpose Building (Covered Court) at Brgy. San Juan, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	28-Jan-25	18-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion (Construction) of Multi-Purpose Building (Covered Court and Stage). This includes construction of stage at rear side, construction of 3 layered concrete bleachers at rear side, installation of steel bleachers at front side and installation of end wall cover at left and right side. This also includes plastering, masonry and steel painting, installation of basketball goal post and electrical works including installation of high-bay lights and scoreboard.
300226120787000	25EI0169 - Completion of Multi-Purpose Building at Barangay Masaguisi, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	31-Jan-25	20-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of 2-Storey Multi-Purpose Building at Barangay Masaguisi, Bongabong, Oriental Mindoro (spiral stairs 1m width, sliding and awning windows at front, left, right and rear side of the 2nd floor of the building, additional sliding windows at the ground floor replacing existing jalousie windows of the existing ground floor, with tiles and ceilings for toilets and floorings of 2nd floor of the building, additional tiles for the left side of the existing ground floor, with complete paintings for masonry, wood and steel, complete electrical works and with plumbing works). See details and plans.
300226120788000	25EI0170 - Completion of Multi-Purpose Building at Barangay Lisap, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	31-Jan-25	25-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Completion of 1 unit Multi-Purpose Building (Covered Court and Stage). The Project includes structural works such as additional 6 columns and beams including frames on both sides, construction of stage and bleacher at right side and installation of flashing.
300226120789000	25EI0171 - Completion of Multi-Purpose Building at Barangay San Isidro, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	31-Jan-25	20-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court)(18 m x 30 m), Phase II. This includes construction of stage, construction of concrete bleachers, installation of end wall cover at left and right side, plastering, masonry and steel painting, installation of basketball goal post and electrical works including installation of high-bay lights.
300226120791000	25EI0172 - Rehabilitation of Multi-Purpose Building at Barangay Mapang, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	05-Feb-25	25-Feb-25	03-Jun-25	13-Jun-25	GoP - Current Budget Year	₱2,970,000.00		₱2,970,000.00	Rehabilitation of 1-Unit 2-Storey Multi-Purpose Building. The project includes earthworks, structural works, and the extension of the second floor, along with concrete finishing and wall painting for new structures and demolition. It also involves tile installation (including interior floors on the second floor and stair) and roof installation, including rafters, purlins, gutters, flashing, and downspouts. Additionally, the scope includes installation of ceiling, doors and windows, decorative stonework, louver blocks, electrical works and mechanical works.
300226120802000	25EI0173 - Construction of Multi-Purpose Building at Barangay Aplaya, Bongabong, Oriental Mindoro, Phase II	Construction Section	No	Competitive Bidding	31-Jan-25	20-Feb-25	13-Mar-25	21-Mar-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Construction of 1-unit two(2) storey Multi-Purpose Building at Barangay Aplaya, Bongabong. This includes earthworks, reinforced concrete works, finishing and other civil works such as termite control works, storm drainage and sewerage system, plumbing works, installation of ceilings, installation of steel doors and frames, aluminum glass door and windows, wooden doors, waterproofing, installation of glazed and unglazed tiles, plastering, masonry painting, masonry works, installation of stainless railings (ramp) and electrical works.
300226120827000	25EI0174 - Construction of New Municipal Building in Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	05-Feb-25	25-Feb-25	13-May-25	23-May-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Construction of 1-Unit 3-Storey Multi-Purpose Building. This includes earthworks, masonry and structural reinforced concrete works for footing, footing tie beam and wall footing.
300226120827000	25EI0175 - Construction of Multi-Purpose Building at Barangay Hagan, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	21-Jan-25	13-Feb-25	07-Aug-25	15-Aug-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Construction of a 1-unit Multi-Purpose Building (Covered Court) measuring 18.00m x 30.00m, which includes embankment, reinforced concrete for column footings, column, footing tie beams, slab, beams, corbels, and gutters. The project also involves the fabrication and installation of trusses, roofing works, and downspouts.
300226120829000	25EI0176 - Construction of Multi-Purpose Building, Barangay Aplaya, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	28-Jan-25	18-Feb-25	07-Aug-25	15-Aug-25	GoP - Current Budget Year	₱4,950,000.00		₱4,950,000.00	Construction of Multi-Purpose Building (Health Center). This includes earthworks, civil works, masonry painting ( painting of perimeter walls, beams and column), steel painting (painting of steel trusses, purlins and railings), roofing works, fabrication and installation of stainless steel signages, decorative stone, air conditioning of (barangay captain's office and session hall), and plumbing works (sewer lines, cold water lines, septic tank and plumbing fixtures).
310303102105000	25EI0177 - Retrofitting / Strengthening of Permanent Bridges: Batangan Bridge, Batangan, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	31-Jan-25	20-Feb-25	22-May-25	27-May-25	GoP - Current Budget Year	₱44,100,000.00		₱44,100,000.00	Retrofitting / Strengthening of 45.60 L.M., 3-spans, 2-lanes RCDG Br. Repair of cracks at deck & girders using epoxy injection prior to the Strengthening of Deck using grid arrangement of carbon fiber sheet and for concrete girder using carbon fiber sheet (2 layers) and plates. Asphalt overlay (40mm thk.) of 56.60 L.M. @ Approaches A & B including 10m transition. Repaint of Concrete Railings.



310303102106000	25EI0178 - Retrofitting / Strengthening of Permanent Bridges: Hagan Bridge, Hagan, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	31-Jan-25	20-Feb-25	13-May-25	23-May-25	GoP - Current Budget Year	₱24,990,000.00		₱24,990,000.00	Retrofitting / Strengthening of 24.6 L.M., 2-spans, 2-lanes RCDG Br. Repair of cracks at deck & girders using epoxy injection prior to the Strengthening of Deck using grid arrangement of carbon fiber sheet and for concrete girder using carbon fiber sheet (2 layers) and plates. Asphalt overlay (40mm thk.) of 56.60 L.M. @ Approaches A & B including 10m transition. Repaint of Concrete Railings.
310303102107000	25EI0179 - Retrofitting / Strengthening of Permanent Bridges: Nawa Bridge, Morente, Bongabong, Oriental Mindoro	Construction Section	No	Competitive Bidding	31-Jan-25	20-Feb-25	13-May-25	23-May-25	GoP - Current Budget Year	₱29,890,000.00		₱29,890,000.00	Retrofitting / Strengthening of 30.76 L.M., 2-spans, 4-lanes RCDG Br. Repair of cracks at deck & girders using epoxy injection prior to the Strengthening of Deck using grid arrangement of carbon fiber sheet and for concrete girder using carbon fiber sheet (2 layers) and plates. Repaint of Concrete Railings.
300116201297000	25EI0180 - Concreting of Brgy. Sta. Maria to Brgy. G. Antonino FMR, Brgy. Sta. Maria and Brgy. G. Antonino, Gloria, Oriental Mindoro	Construction Section	No	Competitive Bidding	26-Feb-25	18-Mar-25	24-Mar-25	03-Apr-25	GoP - Current Budget Year	₱9,950,000.00		₱9,950,000.00	Concreting of Brgy. Sta. Maria to Brgy. G. Antonino FMR, Brgy. Sta. Maria and Brgy. G. Antonino, Gloria, Oriental Mindoro. Road Length=508.00 m (1.0160 Lane KM), Pavement Width=5.00 m, Pavement Thickness=0.23 m, Gravel Shoulder Width=1.00m. Construction of Retaining Walls, Length=446.25 L.m. Removal and Replacement of existing RCPC by 4 lines RCPC 1-0.61m dia. x 7.00m. Provide S-Type Headwall Both Sides. See Plan and Details.
300101200001000	25EI0181 - Construction of School Building, Anoling High School, Barangay Anoling, Pinamalayan, Oriental Mindoro	Construction Section	No	Competitive Bidding	04-Mar-25	24-Mar-25	30-May-25	09-Jun-25	GoP - Current Budget Year	₱9,950,248.76		₱9,950,248.76	Complete construction of a one-storey three-classroom school building 9.50m x 27.00m with three units of CR, including site preparation (demolition of existing structures and embankment)
300101200001000	25EI0183 - Construction of School Building, Buli High School, Barangay Buli, Pinamalayan, Oriental Mindoro	Construction Section	No	Competitive Bidding	04-Mar-25	24-Mar-25	13-May-25	23-May-25	GoP - Current Budget Year	₱9,950,248.76		₱9,950,248.76	Complete construction of a one-storey three-classroom school building 9.50m x 27.00m with three units of CR, including site preparation (rock excavation and embankment)
300202510000800	25EI0184 - Construction of Rainwater Collector System, Bongabong-Bulalacao, Oriental Mindoro	Maintenance Section	No	Competitive Bidding	05-Mar-25	24-Mar-25	27-Mar-25	03-Apr-25	GoP - Current Budget Year	₱2,605,500.00	₱2,605,500.00		Complete construction of 8 units Rainwater Collector System. This includes earthworks, masonry works, concrete works, plastering, painting works and plumbing works for the Reinforced water storage tank (2 meters x 2 meters x 2 meters).
200000100019000	25EI0185 - Repair/Maintenance of Wawan Revetment 3, Brgy. Manaul, Mansalay, Oriental Mindoro	Maintenance Section	No	Competitive Bidding	14-May-25	03-Jun-25	13-Jun-25	19-Jun-25	GoP - Current Budget Year	₱2,000,000.00	₱2,000,000.00		Repair and Maintenance of Flood Control Structure Sta. 0+008.60 - Sta. 0+018.00, Sta. 0+067.20 - Sta. 0+098.00 and Sta. 0+223.00 - Sta. 0+232.80. Net Length = 50.00 L.m.
200000100019000	25EI0186 - Repair/Maintenance of DILG Building Bureau of Jail Management and Penology Roxas District Jail Building San Isidro, Roxas, Oriental Mindoro	Maintenance Section	No	Competitive Bidding	14-May-25	10-Jun-25	16-Jun-25	19-Jun-25	GoP - Current Budget Year	₱2,000,000.00	₱2,000,000.00		Repair and Rehabilitation of Roxas District Jail Building. This includes concrete works, finishing works, plumbing works, painting works, roofing works & electrical works.
Total	139									1,767,230,854.59	6,605,500.00	1,760,625,354.59	

Prepared by:

ALELI OLL J. MANALAYSAY  
Head, BAC Secretariat

Recommended by:

EMMANUEL A. MANALAYSAY  
BAC Chairperson

Approved by:

ANNIELYN E. PADOLLO  
Head of the Procuring Entity