

Republic of the Philippines DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS OFFICE OF THE SECRETARY Manila

June 14, 2017

MEMORANDUM

MARK A. VILLAR 5 FOR

Secretary This Department

This refers to the herein letter dated 01 June 2017 of Regional Director Melvin B. Navarro of National Capital Region (NCR) endorsing the request of OIC-District Engineer Corazon V. Cabatbat, Las Piñas-Muntinlupa District Engineering Office for the Modification of hereunder stated project based on FY 2017 General Appropriation Act (GAA).

Project Description		Physical Target / Cost	
As per GAA	As Modified	Original	Modified
UACS # 292004020200471		124	93.5
Locally Funded Projects –VIILP, Flood Control and Drainage - Drainage/Protection Works : Construction/Improvement of Slope Protection along Balimbing Creek, Barangay Putatan, Muntinlupa City <i>(Construction of Flood</i> <i>Mitigation Structure)</i>	Locally Funded Projects – VIILP Flood Control and Drainage - Drainage/Protection Works : Construction of Slope Protection at Balimbing Creek, Brgy. Poblacion, Muntinlupa City (Construction of Flood Mitigation Structure)	/ lineal meter	lineal meter
		Unit Cost (P'000)	Unit Cost (P'000)
		P80.645T/ lineal meter	P106.952T/ lineal meter
		Allocation Cost (P'000)	Estimated Cost (P'000)
		₽10,000	₽10,000

Reason/s for Modification

In conformity to the procedure in the request for modification of project title, listed below are the facts for consideration that should justify the approval of the same.

- There are revisions in the location, as can be verified in the approved plans. It was transferred on the opposite side which is at Barangay Poblacion. Due to scouring of soil on the said location, construction of Rataining 1. Wall is considered because of its durability instead of Grouted Riprap. Due to these changes, there will be an increase of unit cost per lineal meter at the approved Plans and Program of Work.
- 2. There are revision in the station limits due to the existing Grouted Riprap as per original plan based on original location at Brgy. Putatan;
- 3. Based on the original location, it was requested and intended for construction of grouted riprap having a target of 124 lm, however as per approved plan it was designed as Retaining Wall with a height of 5.0m and a target of 93.5lm

Finding the herein request for modification in order, it is respectfully recommended to the Secretary for his consideration and approval.

ROMEO S. MOMO Undersperetary for Regional Operations in Luzon

APPROVED / DISAPPROVED :



2.4 aap/AVS/ERP/RSM



Copies of the approved project modification requests will be forwarded to the office of Undersecretary Note : Maria Catalina E. Cabral.