Project

Republic of the Philippines DEPARTMENT OF PUBLIC WORKS AND HIGHWA OFFICE OF THE SECRETARY

Manila

July 26, 2021

MEMORANDUM

33

FOR

MARK A. VILLAR Secretary

This Department

This refers to the memorandum dated 22 July 2021 of DPWH Region XIII Director POL M. DELOS SANTOS endorsing the request of District Engineer MARCELINO M. OPERARIO, Surigao del Norte 2nd, District Engineering Office, for the approval of Modification of the hereunder project covered by CY 2021 General Appropriation Act (GAA), to wit;

As per GAA/Original			As Modified		
/		Project	Description		
UACS No. 300108200285000 Project ID : P00550447MN Local Program - Flood Control and Drainage - Drainage / Protection Works - Construction / Repair / Rehabilitation / Improvement of Various Infrastructure including Local Projects Construction of Road Slope Protection Structure along Sungao - Agusan West Coastal Road Sta, 39+773 - Sta.		Local Program - Flood Control and Drainage - Drainage Protection Works - Construction / Repair / Rehabilitation Improvement of Various Infrastructure including Loca Projects Construction of Road Slope Protection Structure alon Surigao - Agusan West Coastal Road Sta. 39+ 780 - Sta			
39+983, Malimono, Type of Work/ Physical Target	Surigao del No	Allocation	39+904.38, Malimo Type of Work/ Physical Target	unit Cost	Estimated Cost
CW1 - Construction of Slope Protection Structure/		P91,675,000.00	CW1 - CW1 - Construction of Slope Protection Structure/ 3,838.46 sq.m.	P23,883.28/ sq.m.	# 91,675,000.00
0.00 sq.m.			3,030.40 54.111.		
0.00 sq.m. EAO	.)≢:	P 3,325,000.00	EA0		P 3,325,000.00

in the FY 2021 GAA.

- Revised station limits from Sta. 39+773 Sta. 39+953 to Sta. 39+780 Sta. 39+904.38, an offset of 7-meters from the
 original start limit to prelude the existing waterway and to prior to prove to slope failure.
- The original station limits that is not included in the revised station is non-implementation due to existing waterway.
- The scope of works involve drilling, installation & grouting of permanent ground anchors, installation of erosion control
 mat, installation of active wire mesh system and apelication of hydroseeding for vegetation, considering that these are
 the major work items of the project.
- The derived unit cost is due to the design requirements as reflected in the approved design plans and relative to the attached evaluation/recommendations of Bureau of Construction (BOC).

Complem Cur M u Cat

Based on our evaluation, the submitted request for project modification is in order, hence, it is respectfully recommended to the Secretary for his consideration and approval.

Undersecretary for Regional Operations in Mindanao

APPROVED/DISAPPROVED:

71/

MARK A. VILLAR Secretary 2.3 aap/LCA/AVS/AGC/ERP Cepartment of Public Works and Highways Office of the Secretary