



APR 14 2023

Republic of the Philippines  
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS  
**OFFICE OF THE SECRETARY**  
Manila

**MEMORANDUM**

**FOR : MANUEL M. BONOAN**  
Secretary  
This Department

This refers to the memorandum dated **February 27, 2023**, of **DPWH Region V, Regional Director VIRGILIO C. EDUARTE, DPWH**, endorsing the requesting for the approval of the **Modification**, of the **District Engineer SALOME M. SARTILLO, DPWH Albay 3<sup>rd</sup> DEO, Paulog, Ligao City**, of the project under FY 2023 General Appropriation Act (GAA), to wit:

As per GAA/Original			As Modified		
Project Description					
UACS: 310105100895000 Project ID: P00713005LZ					
ORGANIZATIONAL OUTCOME 1 : Ensure Safe and Reliable National Road System			ORGANIZATIONAL OUTCOME 1 : Ensure Safe and Reliable National Road System		
Asset Preservation Program - Rehabilitation/ Reconstruction/ Upgrading of Damaged Paved Roads - Secondary Roads			Asset Preservation Program - Rehabilitation/ Reconstruction/ Upgrading of Damaged Paved Roads - Secondary Roads		
Albay West Coast Rd - K0495 + 042 - K0495 + 506			Albay West Coast Rd - K0494 + 955 - K0495 + 256		
Physical Target	Unit Cost (P'000)	Allocation (P'000)	Physical Target	Unit Cost (P'000)	Allocation (P'000)
CW1 – Rehabilitation of Paved Road / 0.928 Lane Km	15,709.569 / Lane Km	14,578.48	CW1 – Reconstruction to Concrete Pavement / 0.596 Lane Km	24,460.537 / Lane Km <i>48.8 m/km.</i>	14,578.48
EAO –		297.52	EAO –		5,425.00
Total:		14,876.00	Total:		14,876.00

**Justification:**

- Decrease in physical target from 0.928 Lane Km to 0.596 Lane Km was due to allocated amount not sufficient to complete the original target as per CY 2023 GAA;
- The work involves Reconstruction: Raising of Grade of existing carriageway preventing water from running into the carriageway, including additional outer lanes (widening 2-3 lanes) with masonry;
- The adjustment on the new Station Limits was due to perennial problem on that flooded section brought about by heavy rains and occurrence of typhoon thereby portions of the section is a close traffic road;
- The recommended new location in station limits is to prioritize the new road section that needs immediate repair/priority DPWH Budget Proposal;
- The adjustments made on Station Limits was due to flooding causing accident to motorists;
- Provision of complete road features such as drainage (both sides), including 3 Barrel Box Culvert and gravel shoulder for bicycle lane and pedestrians;

- Shortening of Physical Target was due to the adjustment of unit cost using the 2nd Quarter CMPD, 1st semester Standard Labor Rates.

Attached are the following supporting documents:

- Certificate of Reasonableness of Cost Estimate, Certificate of Availability of Funds, Program of Works, Detailed Unit Price Analysis, Geotagged Photos and Detailed Engineering Design Plan.

Based on our evaluation, the submitted request for modification of the said project is in order. Hence, the said request is hereby recommended for the Secretary's consideration and approval.



**ANTONIO V. MOLANO, JR., CESO III**

Assistant Secretary for Regional Operations

in NCR, Regions III, IV-A, IV-B, V, VI, VII and VIII

**Recommending Approval:**



**MARIA CATALINA E. CABRAL, Ph.D., CESO I**

Undersecretary for Planning

and Public-Private Partnership Services



**ROBERTO R. BERNARDO, CESO I**

Undersecretary for Regional Operations

in NCR, Regions III, IV-A, IV-B, V, VI, VII, and VIII

**APPROVED/~~DISAPPROVED~~:**



**MANUEL M. BONOAN**  
Secretary

2.6 BCL/RRB

Project ID: P00713005LZ

Department of Public Works and Highways  
Office of the Secretary



WIN3F07188